

MATERIALS SOURCE GUIDE

August 2023



CONSTRUCTION FIELD SERVICES
DIVISION

Foreword

This manual has been prepared to give information and guidance to personnel associated with sampling, testing and inspection of materials used in Michigan Department of Transportation projects. Its purpose is to supplement the Materials Quality Assurance Procedures (MQAP) Manual, Hot Mix Asphalt (HMA) Production Manual, Procedures for Aggregate Inspection, Density Control Handbook, and the Michigan Construction Manual to standardize procedures and assure adequate, uniform quality control.

Buy America step certification is required for pay items and materials as listed in the document located at the following web link:
http://www.michigan.gov/documents/mdot/MDOT_BuyAmericaStepCertPayItems_401954_7.pdf. Please also review the Special Provision for Source of Steel and Iron (Buy America), 20SP105(A) and the Special Provision for Source of Construction Materials, 20SP105(B) available under the heading of MDOT Supplemental Specs and Special Provisions (SS/SP) through the MILogin system.

For copies of the most recent Materials Source Guide you can:

Download from the internet at web address:

https://www.michigan.gov/mdot/0,4616,7-151-9622_11044_11367_68095---,00.html

Or Navigate by:

```
www.michigan.gov/mdot
  \
   Business
     \
      Construction
        \
         2020 Standard Specifications and Reference Publications
           \
            Materials Source Guide
```

Periodically check the website for updates to the Materials Source Guide. Updated guides can be downloaded and printed.

Table of Contents

Title	Page
Definitions	4
Index (In reference to the Materials Acceptance Requirements Table)	11
Materials Acceptance Requirements, including Special Instructions, copied from the MDOT Materials Quality Assurance Procedures Manual Chapter 6	28
Approved Suppliers List.....	75
Approved Manufacturers List.....	79
Qualified Products List	91
Selecting and Shipping Samples	124
Appendix	
Visual Inspection Items by Quantity - Alphabetical	126
Visual Inspection Items by Quantity - by Specification Number	129

This manual is in accordance with the 2020 Standard Specifications for Construction.

Definitions

(References to the Materials Quality Assurance Procedures Manual-MQAP)

Basis of Acceptance: Refers to the method by which materials incorporated into MDOT projects are accepted. Below is a list of all the current Basis of Acceptance methods used by MDOT for acceptance of materials.

- Visual Inspection (VI): (See MQAP Section 1.06) Materials which may be visually inspected by MDOT personnel for acceptance or rejection. When a maximum VI limit is given for materials with another specified basis of acceptance, materials may be accepted by VI up to maximum VI quantities as indicated for that material, per item, per contract. (NOTE: All materials should be visually inspected prior to incorporation into the job without quantity limit, and may be rejected on that basis even though material may be acceptable on another basis.)
 - Qualified Product List (QPL): (See MQAP Section 5.01) Products that have been tested and/or evaluated by MDOT and found to meet performance and/or other specification requirements. A Qualified Products List (QPL) of these products is maintained within this document. All QPL materials must be documented per Section 5.01 of the MQAP.
- General Certification (Gen Cert): (See MQAP Section 2.01) When this certification is specified as the basis of acceptance in the contract documents, it must be provided in accordance with Section 2.01 of the MQAP. A general certification must include a general description of the material(s), a list of the applicable specifications (ASTM, AASHTO, MDOT or other designations as appropriate), and a statement that the material(s) conforms to these specifications.
- Test Data Certification (Test Data Cert): (See MQAP Section 2.01) When this certification is specified as the basis of acceptance in the Materials Acceptance Requirements Table, in addition to the requirements of a General Certification, the certification must also include laboratory test report(s) for samples obtained from the same lot(s), batch, heat, etc. of material represented by the certification and tested according to applicable specifications (ASTM, AASHTO, MDOT).
- Approved Manufacturer (Appr Mfr): (See MQAP Section 2.02) A manufacturer who has submitted quality control documentation and/or material samples, and has been given approval status to certify specific material(s). General Certification per the requirements of Section 2.01 of the MQAP must accompany all Approved Manufacturer shipments to either an Approved Supplier location or the MDOT project site. Strict adherence to the requirements for Certification Documentation and Distribution is required of all Approved Manufacturers.
 - Approved Supplier: (See MQAP Section 2.02) When Approved Manufacturer is specified as the basis of acceptance in the contract documents, the material must be supplied by the manufacturer or, without modification to the material, by an Approved Supplier. An Approved Supplier must recertify Approved Manufacturer material(s). Strict adherence to the requirements for Certification Documentation and Distribution is required of all Approved Suppliers for the recertification of material(s). All original Approved Manufacturer General Certification(s) must accompany the material(s) shipment to the MDOT project site. When Approved Manufacturer is specified, a supplier may not distribute or recertify material(s) unless they have been granted Approved Supplier status.

- Special Provision: Revisions and additions to the Standard and Supplemental Specifications applicable to an individual project. Special Provisions have been reviewed and approved for use by MDOT. Materials acceptance may be defined by these documents included in the project proposals.
- Fabrication Inspection (Fabrication Inspection): Materials subjected to Fabrication Inspection are those that are typically manufactured offsite and shipped to the project. Refer to the proper subsection of the Structural Fabrication Quality Manual (SFQM) to find the requirements of the various Fabrication Inspections currently performed by MDOT.
- Acceptance Testing (Test): Sampling and testing of a material to determine compliance with specification requirements prior to incorporation into the project. Acceptance testing is the required basis of acceptance for some materials, as indicated in the contract documents, but may be applied to all materials regardless of the basis of acceptance.

Other Definitions

Manufacturer: A producer or fabricator of materials with control over the quality, workmanship and handling of material.

Supplier: A supplier has no control, other than through careful handling, over the quality and workmanship of material.

Certification Documentation (See MQAP Section 2.01)

Where more than one piece of paper is included in the certification document, all pages must be numbered (__ of __) and include Contract I.D. in order to reunite them should they become separated.

Stencil, stamp, or otherwise mark all certified material prior to delivery to a supplier or project. This mark must identify the AASHTO, ASTM, or MDOT specification that the material meets, to allow the material to be recognized and checked against the certification document.

General Certification – This documentation must consist of all of the following:

- Company name, address and contact information.
- Date the certification was produced.
- Contract number (Control Section/Job Number).
- Name of contractor.
- If material is certified by a supplier or Contractor, the manufacturer's name must be included on the certification.
- A list of all applicable specifications (ASTM, AASHTO, MDOT or other designations as appropriate) which the material is certified to meet.
- Any applicable specification modifier such as class, grade, type, etc.
- Name of material (MDOT designation and Spec Number).
- Identification markings on shipment as required by the General Materials Certification Procedures, in the Quality Assurance Procedures Manual, Section 2.01.03.B.

- A statement, signed by a responsible representative of the manufacturer, supplier, or Contractor that the material represented by the certification meets all MDOT listed specification requirements.

Test Data Certification - When this certification is specified as the basis of acceptance in the Materials Acceptance Requirements Table, in addition to the requirements of a General Certification, the following information must also be included:

- Laboratory test report(s) for samples obtained from the lot(s) of material represented by the certification and tested according to applicable specifications (ASTM, AASHTO, MDOT).

Certification Distribution

All certification documents except those issued by Approved Manufacturers/Approved Suppliers must be distributed as follows: Submit to the Construction/Project Engineer. The Contractor is ultimately responsible for all materials documentation distribution to the Project Engineer's office.

Approved Manufacturer/Approved Supplier Certifications must follow the above distribution requirements with the addition of one a copy being mailed, emailed, or faxed on the date of shipment to:

Michigan Department of Transportation
Construction Field Services Division
Materials Control
P.O. Box 30049
Lansing, Michigan 48909
Facsimile: (517) 322-5664
Email: MDOT-MaterialsControl@michigan.gov

Certifications and Recertification

Information required on certifications may vary from one material to the next. The following examples of certification documents are only provided for reference.

Materials Source List (See MQAP Section 1.04)

A completed and signed Materials Source List (Form 501) is required project documentation, and required for payment of associated items of work. The Materials Source List is not a substitute for other required material quality control and quality assurance documentation. Prime contractors are responsible for accurate submission of the Materials Source Lists for all materials including their subcontractors.

MATERIALS SOURCE LIST

[Clear Form](#)

File 300

INSTRUCTIONS: Use the "Materials Source Guide" for material name and specification number. Enter "SP" for MDOT SPEC NUMBER for materials specified by special provision. To avoid delays, submit as soon as possible. No testing of materials will be conducted until the Engineer has been notified. Contractor to submit form to Engineer in ProjectWise Contractor Inbox. The Engineer will populate the remaining fields and distribute to Region/Transportation Service Center (TSC) Materials Supervisor.

Specification (SPEC), Certifications (CERTS), Visual Inspection (VI), Special Provision (SP), Fabrication Inspection (FI)

CONSTRUCTION/PROJECT ENGINEER CONTRACTOR CONTRACT ID

PROJECT LOCATION

MDOT SPEC NUMBER	MDOT MATERIAL/PRODUCT NAME	TYPE/SIZE or CLASS	APPROXIMATE QUANTITY	SOURCE OF MATERIAL (NAME, ADDRESS, LOCATION, AGGREGATE SOURCE INVENTORY (ASI) NUMBER)	BASIS OF ACCEPTANCE				REMARKS/OTHER
					TEST	CERTS	VI	SP	
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here
									Select an item from list OR type here

Check here if there are any revisions. Mark any revisions with an asterisk.

CONTRACTOR CONTACT NAME	CONTRACTOR CONTACT E-MAIL ADDRESS	PHONE NUMBER	DATE SUBMITTED
ENGINEER REPRESENTATIVE NAME	ENGINEER REPRESENTATIVE E-MAIL ADDRESS	PHONE NUMBER	DATE RECEIVED

Enter Your Company Letterhead/Logo Here
(Name, Address, Contact Info)

General Certification

Date: _____ Name of Contractor: _____

Control Section/Project #: _____ Project/Job Location: _____

We certify that the following described materials/products meet the specification requirements of the Michigan Department of Transportation, ASTM, or AASHTO.

MDOT Material Name: As described in the MDOT Materials Source Guide

MDOT Spec #: As described in the MDOT Materials Source Guide

Lot #, Heat OR Identification:

Class, Grade OR Type:

Size or Weight:

Signature of Company Representative

Printed Name of Company Representative

Title of Company Representative

Distribution: Submit to the Construction/Project Engineer

Enter Your Company Letterhead/Logo Here
(Name, Address, Contact Info)

Approved Supplier Recertification

Contract ID:
Control Section/Job #: _____ Date: _____

Contractor: _____

We certify that the following described material meets the specification requirements of the Michigan Department of Transportation for the above project and this material is certified by the manufacturers indicated below.

MDOT Material Name: As described in the MDOT Materials Source Guide
MDOT Spec #: As described in the MDOT Materials Source Guide
Manufacturer:
Lot, Heat or Identification:
Quantity:
MDOT Material Name: As described in the MDOT Materials Source Guide
MDOT Spec #: As described in the MDOT Materials Source Guide
Manufacturer:
Lot, Heat or Identification:
Quantity:
MDOT Material Name: As described in the MDOT Materials Source Guide
MDOT Spec #: As described in the MDOT Materials Source Guide
Manufacturer:
Lot, Heat or Identification:
Quantity:

All steel, iron, and/or applicable construction materials furnished on this certification is of domestic origin and is in compliance with the project Buy America and Source of Construction Materials provision.

Signature of Company Representative

Printed Name of Company Representative

Title of Company Representative

Distribution: Submit to the Construction/Project Engineer. Submit one additional Copy mailed or faxed to Construction Field Services Division, MDOT, P.O. BOX 30049, LANSING, MI 48909. FAX # (517)322-5664 or via email to MDOT-MaterialsControl@michigan.gov , complete on date of material Shipment.

Materials Acceptance Requirements Table Definitions

Sampling Frequency: (If Required) Amount of material or number of items, as defined in the Materials Acceptance Requirements Table or other contract documents, which require a sample when submitting material to the Construction Field Services Division for testing.

Size of Sample: Minimum size of sample required for testing as defined in the Materials Acceptance Requirements Table or other contract documents.

Maximum VI Quantity: Maximum amount of material which can be accepted by visual inspection for each material, per item, per project.

Remarks: Special notes pertaining to individual materials.

Special Instructions: More detailed information pertaining to particular types of materials, and referenced in "Remarks" or listed in the Materials Source Guide.

Note: When the Basis of Acceptance is not "Test", the sampling criteria provided may be used as guidance if the Project/Construction Engineer determines there may be a problem with the material and requests sampling and testing.

Alphabetical Index
 To 2020 Material Specification Numbers
 In The Material Acceptance Requirement Table

-A-

ABS Pipe.....	909.07A1
Abrasive, Low Dusting Blasting	715.02 & 716.02
Abutment Backfill	902
Adhesive Systems for Structural Anchors and Lane Ties	712.03J
Adhesive Systems for Dowel Bars & Tie Bars	603.03B2
Adjusting Rings for Manholes and Drainage Structures (Recycled Rubber)	909.01
Adjusting Rings for Manholes and Drainage Structures (Precast Concrete)	913.06
Admixture, Air Entraining.....	903.01
Admixture, Latex Emulsion for Concrete	903.03
Admixture, Mineral Filler, Bituminous Mixtures	902
Admixture, Pozzolanic (Fly Ash) for Concrete	901.07
Admixture, Water Reducing, Retarding, and/or Liquid Accelerators	903.02
Admixture for Expansive Grout Type E-1	1005.02C
Aggregates.....	902
Air Entraining Admixture.....	903.01
Aluminum Alloy Pipe (Corrugated)	909.05B
Aluminum Alloy Sheets, Corrugated.....	909.05B
Aluminum Alloy Structural Plate	Misc. #9
Aluminum Sheets for Signs	919.02A3
Anchor Bolts, Studs, Rods.....	908.14
Anchor Bolts and Nuts, Other Purposes	908.14D
Anchors, Concrete Adhesive Bonded (Resin).....	712.03J
Anchors, Expansion	712.03K
Approved Manufacturers	Page 58
Approved Suppliers	Page 54
Arrow Bars, Lighted.....	922.07
Arrow Boards, Type C Solar Assist	922.07
Asphalt Binder.....	904.03A
Asphalt Emulsion, Bond Coat.....	904.03C
Asphalt Release Agents	501.02
Asphalt Rubber, Overband Crackfill	502.02B
Assemblies, Load Transfer.....	914.07

-B-

Back-up Plates for Guardrail	908.11C
Backer Rod, Foam	914.04B
Backfill, Abutment	902
Band Clamps, Strain Pole	921.05A
Bar Chairs	905.03D
Barbed Wire	907.03B
Barricades	922.03E
Barrier Reflectors	922.04A
Barrier Reflectors, Temporary	922.04A
Bases, Precast Concrete.....	913.07
Baskets, Dowel, Load Transfer	914.07
Beam Guardrail.....	908.11A
Beam Plates, Sealant for Perimeter	713.02B
Bearings, Elastomeric	914.12A
Bent Tie Bars, Lane Ties.....	914.09
Biaxial Geogrid, Road Grade.....	910.06
Bituminized Fiber Joint Filler	914.03
Bituminized Fiberglass and Cotton Fabric	Misc. #14
Bituminous Materials (Asphalt Binder).....	904.03A
Blasting Abrasive, Low Dusting	715.02 & 716.02
Blasting Abrasive, Steel Grit.....	715.02
Block, Concrete.....	913.05
Bolts, Mechanical Expansion Anchors.....	914.10
Bolts, Adhesive Anchor Systems.....	914.10
Bolts, Anchor, Studs, Rods.....	908.14
Bolts, Anchor, Other Purposes	908.14D
Bolts, High Strength	906.07
Bond Release Agent, Concrete (Dowel Bars).....	914.07A3
Bonded Anchors, Concrete Adhesive	712.03J
Brick, Clay and Sand Lime	913.03
Brick, Concrete.....	913.03C
Bridge Deck Drain Extensions, Fiberglass.....	909.08C
Bridge Railing, Base Plate and Post Elements	908.09A
Bridge Railing, Hardware	908.09C
Bridge Railing, Tube, Parapet	908.09B

Bridge Railing, Tube, Rectangle (Galvanized).....	908.09A
Bridge Sign Connections.....	810.030
Bushings for Pins and Link Plates.....	707.02
-C-	
Cable, Electrical.....	918.03
Cable, Prestress Strand.....	905.07
Calcium Chloride.....	922.12A
Calcium Chloride Concrete Accelerators.....	903.04
Cantilever, Sign Support.....	919.07
Caps, Expansion for Dowel Bars.....	914.07C
Casing, Steel Pipe.....	909.05D
Casing, Foundation.....	919.10
Cast Iron Pipe.....	Misc. #2
Castings, Miscellaneous Metals (Manhole).....	908
Catch Basins.....	908
Cedar Posts (Wood Fence).....	912.07B
Cement.....	901
Certification Verification of Cement.....	901
Certification Verification of Expansive Grout.....	1005.02C
Chain Link Fence Fabric.....	907.04A
Chairs, Steel Reinforcement.....	905.03D
Chemical Fertilizer for Grass Seeding.....	917.09
Chemical Weed Sprays.....	917.15
Class A, B and F Bury Plastic Pipe.....	909.06
Clay Brick.....	913.03
Clay Pipe.....	Misc. #3
Closed-Cell Polypropylene Foam Joint Filler.....	914.03C
Coarse Aggregate.....	902
Coating for Dowel Bars.....	914.07A2
Coating for Rebar, Epoxy.....	905.03
Coating Systems for Steel Structures, Hangers Assemblies and End Diaphragms (Prime, Intermediate, Top).....	915
Cobblestone.....	916.01A
Cold Applied Pipe Joint Sealer (Mastic).....	909.09
Cold Plastic Pavement Marking, Permanent.....	811.03D4

Cold Plastic Pavement Marking, Temporary (Tape)	922.06A
Column Break-Away Sign Support	919.06
Compost.....	917.07
Compression Gasket.....	909.03
Concrete Adhesive System for Bonded Anchors (Resin).....	712.03J
Concrete Barriers, Temporary	922.04
Concrete Barrier Reflectors	922.04A
Concrete Bases, Precast.....	913.07
Concrete Block.....	913.05
Concrete Brick.....	913.03C
Concrete End Sections, Precast.....	909.04E
Concrete Expansion Anchors	712.03K
Concrete Pipe, Reinforced and Non-Reinforced.....	909.04A - C
Conduit, Electrical	918.01, 918.01A, B, D, F
Conduit, Electrical (Polyethylene).....	918.01D & E
Cones, Traffic.....	922.03A
Contraction Baskets	914.07
Copper Sheet (Waterstop).....	908.08
Corrugated Aluminum Alloy Pipe.....	909.05B
Corrugated Aluminum Alloy Sheets.....	909.05B
Corrugated Poly-Pipe, Culverts and Sewers	909.06
Corrugated Poly-Tubing, Underdrains	909.07B
Corrugated Plate, Structural	Misc. #8
Corrugated Steel Pipe	909.05A
Corrugated Steel Pipe (Polymer Coated)	909.05A1
Corrugated Steel Sheets	909.05A1
Cotton Fabric, Bituminized	Misc. #14
Coupling Bands.....	909.05A3
Cover, Sign	922.02D
Covers and Lids, Manholes	908
Crack Injection	914.06
Culvert, Cast Iron	Misc. #2
Culverts, Class B.....	909.06
Curing Compound.....	903.06
Curtain, Turbidity	916.07
Cut-offs for Piling.....	906.05

-D-

Deck Drain Extensions, Bridge.....	909.08C
Deformed Steel Bars for End-of Pour Joint Devices	914.08
Delineator Posts, Flexible.....	919.03D
Delineator Posts, Steel.....	919.03D
Delineator Reflectors.....	919.03A, B
Dense Graded Aggregate	902
Detectable Warning Surfaces.....	803.02B
Dimension (Sawed) Posts, Wood.....	912.08
Ditch Lining (Geotextile Blanket)	910.03A
Dowel Bar Grouting Systems	603.03B2
Dowel Bars for Load Transfer (Steel)	914.07
Dowel Baskets, Load Transfer	914.07
Downspouts, Bridge Deck	909.08A
Downspouts, Culvert	909.08B
Drain Pipe (Underdrain)	909.07A, B
Drainage Marker Post	909.10
Drainage Casting, Misc. Metals.....	908
Drainage Structures, Precast Reinforced Concrete	913.06
Drainage Structure Adjusting Rings, Precast Concrete	913.06
Ductile Iron Castings	908.05
Ductile Iron Pipe.....	Misc. #2
Dust Palliative, Calcium Chloride.....	922.12A

-E-

Edge Drain (Tubing).....	909.07B
Elastomeric Bearings	914.12A
Elastomeric Leveling Pads	914.12B
Electrical Cable	918.03
Electrical Conduit (Galvanized Steel and Non-Metallic).....	918.01A
Electrical Conduit (Polyethylene).....	918.01D
Electrical Conduit (Polyvinyl Chloride)	918.01B
Electrical Traffic Control Devices.....	921.03
Embedded, Galvanic Anodes	712.03Y
Emulsified Asphalt.....	904.03C
Emulsion, Latex Admixture for Concrete	903.03

End Sections, Grate, for Culverts	401.03E
End Sections, Slope, Steel	909.05C
End Sections, Steel	909.05C
End Sections, Precast Concrete	909.04E
End Sections, Guardrail	908.11A
End-of-Pour Joint Devices/Deformed Steel Bars	914.08
Epoxies for Adhesive Systems	712.03J
Epoxy Binder, Joint Spall Repair	914.05
Epoxy Coated Dowel Bars.....	914.07A
Epoxy Coated Steel Reinforcing Bars	905.03
Epoxy Coating for Bar Reinforcement	905.03
Epoxy Coating for Dowel Bars.....	914.07A2
Epoxy Mastic.....	712.03D
Epoxy Resin Adhesive for Crack Injection	914.06
Excelsior Mulch Blankets	917.14B
Expansion Anchors, Structure	712.03K
Expansion Baskets.....	914.07
Expansion Caps for Dowel Bars	914.07C
Expansion Joint Devices, Bridge	706.03K4
Expansive Grout Type E-1, Admixture	1005.02C
External Type Gasket for Pipe.....	909.03
Extruded Aluminum Sections for Sign Panels.....	919.02A1

-F-

Fabric, Bituminous, Cotton, Fiberglass	Misc. #14
Fabric, Filter, for Underdrain (Geotextile Blanket).....	910.03A
Fabric for Chain Link Fence	907.04A
Fabric for Woven Wire Fence.....	907.03A
Fabric Reinforcement, Welded Steel Wire (Mesh)	905.06
Fast Set Patching, Hydraulic Mortar	1006
Fence, High Tensile Wire	907.05A
Fence, Horizontal Rail	907.04C
Fence Fabric, Chain Link	907.04A
Fence Fabric, Woven Wire	907.03A
Fence Gates, Chain Link.....	907.04D
Fence Gates, Woven Wire	907.03F

Fence Pedestrian, Posts and Rail	907.04C
Fence Protective	907.06
Fence Posts, Steel	907.04C
Fence Posts, Wood	(907.03E & 907.05B) 912.07B
Fertilizer	917.09
Fiber Joint Filler, Bituminized	914.03
Fiberglass Fabric.....	Misc. #14
Filter Bags, Geotextile Blanket	910.03A
Filter Fabric for Wrapped Underdrain (Knitted Sock)	910.03A
Fine Aggregate.....	902
Flexible Metal Conduit.....	918.01
Fly Ash, Mineral Filler for Bituminous Mixtures	902
Fly Ash, Pozzolanic Admixture for Concrete.....	901.07
Foam Backer Rod	914.04B
Foundation Piling	906.05

-G-

Galvanic Anodes, Embedded	712.03Y
Galvanized Bridge Tube Railing	908.09B
Galvanized Conduit, Electrical.....	918.01A
Galvanized Slotted Drain Pipe.....	Misc. #5
Galvanized Steel Sheets, Corrugated	909.05A1
Gasket, Compression.....	909.03
Gasket, External Type for Pipe.....	909.03
Geocomposite Wall Joint Drain	910.05B
Geogrid, Biaxial Road Grade.....	910.06
Geotextile Blanket	910.03A
Geotextile Pipe Wrap Liner.....	910.03A
Geotextile Rip Rap Liner	910.03B
Geotextile Separator	910.03C
Geotextile, Stabilization	910.03D
Glare Screen.....	804.01
Glass Beads, Standard	920.02B
Granular Material	902
Grass Seed	917.11
Gray Iron Castings	908.05

Grit, Steel, Blasting Abrasive.....	715.02
Grounding Rods	918.02C
Grounding System	918.02
Grout Under Masonry Plates	712.03X
Grout, For Full-Depth Concrete Pavement Repairs	603.03B2
Grouting Cracks by Pressure Injection, Intrusion.....	914.06
Grouts and Mortars	1005.02A, B, C
Guar Gum Base Adhesive, Mulch Binder	917.14C
Guardrail Anchorage, Bridge, Beam Elements, End Sections, Shoes and Departing End Terminals.....	908.11A
Guardrail Approach Terminals.....	908.11A
Guardrail Hardware	908.11B
Guardrail Offset Blocks, Recycled Plastic or Rubber	912.08Q
Guardrail Posts and Blocks, Wood (Dimension Sawed)	912.08
Guardrail Posts for Beam Guardrail, Steel.....	908.12
Guardrail Reflectorized Washer	908.13
Guardrail Steel Beam Elements	908.11A
Guide Posts	912.07B
Guy Wire, Electrical.....	918.11A
-H-	
H Piling.....	906.05
Handholes, Polymer, Light Weight Composite.....	918.06D
Handholes, Precast.....	918.06
Hanger Assemblies, Coating Systems	915
Hardware, Fence.....	907.04E
Hardware, Guardrail.....	908.11B
Hardware, Sign	919.02C
Headwall, Precast Concrete	401.03E
Herbicide, Spray.....	917.15
High Strength Steel Bolts, Nuts and Washers	906.07
High Tensile Fence Wire	907.05A
Highway Lighting Materials (Luminaires)	918.09
Hollow Load and Non-Load Bearing Block (Concrete).....	913.05
Hot-Poured Joint and Crack Sealant	914.04A
Hydraulic Anchor Systems	712.03J

-I-

Insulation, Blankets and Polystyrene.....903.07C & D
Interim Linseed Oil Curing Compound.....903.07A
Iron Pipe, Cast and Ductile Iron and Fittings Misc. #2

-J-

Jacked-In-Place Steel Pipe 909.05D
Joint Filler.....914.03, 914.03B, 914.03C
Joint Filler, Fiber (Bituminized) 914.03
Joint and Crack Sealant, Hot-Poured914.04A
Joint Sealer, Pipe Gaskets (O-Ring)..... 909.03
Joint Sealer for Pipe, Cold Applied (Mastic) 909.09
Joint Spall Repair Materials..... 914.05
Joint Wall Drain, Geocomposite910.05B

-K-

-L-

Lane Ties 914.09
Latex Base Adhesive for Mulch 917.14C
Latex Emulsion Admixture for Concrete 903.03
Lead Sheet (Waterstop) 908.07
Light Standards..... 918.08
Lighted Arrows922.07A
Limestone Dust, Bituminous Mineral Filler..... 902
Liner for Riprap910.03B
Link Plates for Steel Bridge Construction 906.08
Linseed Oil Interim Curing Compound.....903.07A
Liquid Asphalt, MC & RC-250.....904.03B
Load Transfer, Dowel Bars (Steel) 914.07
Load Transfer Assemblies, Dowel Baskets 914.07
Load-Bearing Block (Concrete) 913.05
Loop Sealant, Traffic921.08B
Low Dusting Blasting Abrasive 715.02 & 716.02
Lumber, Structural..... 912.05
Luminaires 918.09

-M-

Mail Box Posts	912.07B
Malleable Iron Castings.....	908.03
Manhole, Block.....	913.05
Manhole, Brick	913.03C
Manhole Castings	908
Manhole Covers and Lids.....	908
Marking Tape, Cold Plastic, Permanent	811.03D4
Marking Tape, Temporary Lane	922.06A
Masonry Plate, Grout	712.03X
Masonry Units, Precast Drainage.....	913.06
Mastic (Cold Applied Joint Sealer for Pipe)	909.09
Mechanical Reinforcement Splicing.....	712.03L
Membrane, Preformed Waterproofing	914.11
Membrane Curing Compound	903.06
Mesh Reinforcement (Pavement).....	905.06
Metal End Sections	909.05C
Metallic Waterstop, Sheet Copper.....	908.08
Metallic Waterstop, Sheet Lead.....	908.07
Mineral Filler for Bituminous Mixtures.....	902
Mortars and Grouts	1005.02A, B, C
Mulch Anchoring	917.14C
Mulch Binder, Tackifiers, Non-Asphalt Emulsion	917.14C
Mulch Blanket, Excelsior and Straw	917.14B2
Mulch Blanket, High Velocity	917.14B1
Mulch Blanket, Straw.....	917.14B2
Mulching Materials for Nursery Stock.....	917.13

-N-

Non-Load Bearing Block	913.05
Non-Reinforced Concrete Pipe.....	909.04C
Non-Shrink Mortars and Grouts, Type H1 (Non-Metallic)	1005.02B
Nursery Stock (Trees, Bushes)	917.03

-O-

O-Ring, Compression Gasket.....	909.03
---------------------------------	--------

Open-Graded Aggregate	902
Outlet, Drainage Pipe (Underdrain)	909.07C1, 2, & 3
Outlet Ending (Underdrain)	404.02C
Overband Crackfill	502.02B
-P-	
PVC Sanitary Sewer Pipe	909.06
Paint for Coating Existing Steel Structures (Prime, Intermediate, Top)	915
Paint for Pavement Marking	811.03D
Patching, Fast Set Hydraulic Mortar	1006
Pavement Lane Ties	914.09
Pavement Marking Cover (Temporary)	922.06C
Pavement Marking, Standard Glass Beads	920.02B
Pavement Marking, Modified Epoxy	811.03D8
Pavement Marking, Polyurea	811.03D7
Pavement Marking, Thermoplastic, Liquid	811.03D5
Pavement Marking, Thermoplastic, Sprayable	811.03D6
Pavement Marking, Thermoplastic, Preformed	811.03D9
Pavement Marking, Waterborne, Liquid, Paint	811.03D1
Pavement Marking Regular Dry Paint	811.03D3
Pavement Marking Tape, Cold Plastic	811.03D4
Pavement Marking Tape, Type R/NR	922.06A
Pavement Markers, Raised (Temporary)	922.06B
Pavement Reinforcement (Mesh)	905.06
Pavement Tie Bars	914.09
Penetrating Water Repellents	706.03S
Perforated Poly-Tubing, Underdrain	909.07B
Pile Points	906.05
Piling, H Piling and Special Sections	906.05
Piling, Steel Sheet	906.06
Piling, Steel Shells	906.05
Piling, Timber	912.06
Pipe, Cast and Ductile Iron	Misc. #2
Pipe, Clay	Misc. #3
Pipe, Concrete	909.04A - C
Pipe, Corrugated Aluminum Alloy	909.05B

Pipe, Corrugated Polyethylene (CPE/HDPE).....	909.06
Pipe, Corrugated Steel	909.05A
Pipe, Downspouts	909.08A, B
Pipe, Gasket	909.03
Pipe, Plastic, Class A, B and F Bury.....	909.06
Pipe Joint Sealers	909.09
Pipe, Steel Casing.....	909.05D
Pipe, Steel Casing, Foundation	919.10
Pipe Wrap, Geotextile	910.03A
Plastic Drums	922.03
Plastic Guardrail Blocks	912.08Q
Plywood for Signs	919.02A2
Poles, Tower Lighting.....	918.10A
Polyethylene Pipe for Culverts and Sewers(CPE/HDPE)	909.06
Polyethylene Tubing for Underdrain	909.07B
Polymer Coated Corrugated Steel Pipe.....	909.05A1
Polystyrene, Insulation	903.07D
Polyvinyl Chloride Pipe (CPV/PVC).....	909.06
Portable Signs.....	922.07C
Post Tensioning, Tendons.....	905.08
Posts, Delineator, Flexible (Plastic).....	919.03D
Posts, Delineator, Steel.....	919.03D
Posts, Dimension Sawed (Wood).....	912.08
Posts, Drainage Marker.....	909.10
Posts, Mailbox.....	912.07B
Posts, Signs, Steel.....	919.04
Posts, Wood for Fencing	912.07B
Posts, Wood Sign.....	912.08, 919.05
Posts for Chain Link Fence (Steel)	907.04C
Posts for Woven Wire Fence (Steel)	907.03D
Pozzolanic Admixture for Concrete (Fly Ash)	901.07
Precast Concrete Bases.....	913.07
Precast Concrete Box Sections.....	909.04D
Precast Concrete End Sections.....	909.04E
Precast Concrete 3 Sided or Arch Sections.....	909.04G
Precast Concrete Handholes.....	918.06

Precast Concrete Headwalls	401.03E
Precast Reinforced Concrete Drainage Structures	913.06
Precast Sumps.....	913.07
Preformed Waterproofing Membrane	914.11
Premixed Grouts and Mortars, Type H1 (Non-Metallic)	1005.02B
Prestress Strand for Concrete	905.07
Prestressed Concrete Beams.....	708.03A
Protective Coating for Concrete, Water Repellent	706.03S
Protective Fence	907.06

-Q-

Qualified Products List	Page 68
-------------------------------	---------

-R-

R C 250, Liquid Asphalt Waterproofing Primer	904.03B
Railing, Bridge Tube Element (Galvanized).....	908.09B
Raised Pavement Markers (Temporary).....	922.06B
Recertifiers.....	Page 54
Recycled Plastic or Rubber Guardrail Offset Block.....	912.08Q
Recycled Rubber Adjusting Rings	909.01
Recycled Rubber Joint Filler.....	914.03B
Reflective Sheeting	919.02B1
Reflective Sheeting, Temporary Signs	922.02B
Reflectorized Washers, Guardrail.....	908.13
Reflectors, Delineator.....	919.03A, 919.03B
Reflectors, Concrete Barriers	922.04A
Reflectors, Concrete Barriers, Temporary	922.04A
Regular Dry Pavement Marking Paint	811.03D3
Reinforced Concrete Pipe	909.04A
Reinforcing Steel Bars.....	905.03
Release Agents, Asphalt	501.02
Retarding Admixtures.....	903.02
Rip Rap	916.01C
Road Grade Biaxial Geogrid.....	910.06
Rubber, Recycled, Joint Filler.....	914.03B
Rustic Construction, Timber	912.09

-S-

Sand Lime Brick	913.03
Sawn Wood Posts and Blocks.....	912.08
Sealant for Perimeter of Beam Plates	713.02B
Sealer for Pipe Joints, Cold Applied (Mastic).....	909.09
Seeding Mixtures	917.11
Selecting and Shipping Samples	Page 91
Separator, Geotextile	910.03C
Sewer Pipe, Concrete	909.04A - C
Sewer Pipe, PVC Sanitary.....	909.06
Shear Developers (Studs)	906.09
Sheet Copper (Waterstop).....	908.08
Sheet Lead (Waterstop)	908.07
Sheeting, Reflective	919.02B1
Sheeting, Reflective, Temporary Signs.....	922.02B
Shelf Life, Curing Compound (Linseed Oil Base)	903.07A
Shipping and Selecting Samples	Page 91
Shotcrete, Waterproofing	710.03D
Shredded Bark, Mulching Materials.....	917.13
Sign Hardware	919.02C
Sign Paddles.....	922.11
Sign Posts.....	919.04, 919.05
Sign Support, Cantilever	919.07
Sign Support, Truss.....	919.08
Signals, Electrical Traffic Control.....	921.03
Signs, Permanent.....	919.02
Signs, Portable.....	922.07C
Signs, Temporary, Prismatic	922.02
Signs, Temporary, Cover	922.02D
Signs, Temporary, Reflective Sheeting.....	922.02B
Silt Fence (full assembly)	916.02
Silt Fence Geotextile (fabric only).....	910.04
Slag Cement	901.06
Sleeves, Steel for Guardrail.....	908.11C
Sleeves, Steel for Wood Sign Posts	919
Slope Paving Block	913.09

Slotted Drain Pipe, Galvanized.....	Misc. #5
Sod	917.12
Span Wire, Electrical.....	921.02
Splicing, Reinforcement (Mechanical)	712.03L
Sprays, Chemical (Weed Control)	917.15
Stabilization Geotextile.....	910.03D
Standard Mortars and Grouts.....	1005.02A
Steel Barbed Wire	907.03B
Steel Beam Guardrail Elements	908.11A
Steel Castings.....	908.04
Steel Grit Blasting Abrasive.....	715.02
Steel H Piling.....	906.05
Steel Pipe, Jacked-In-Place	909.05D
Steel Posts for Beam Guardrail	908.12
Steel Posts for Fence	907.03D, 907.04C
Steel Posts for Signs.....	919.04
Steel Reinforcing Bars.....	905.03
Steel Sheet, Corrugated Galvanized	909.05A1
Steel Sheet Piling.....	906.06
Steel Sleeves for Guardrail.....	908.11C
Steel Sleeves for Wood Sign Posts	919
Straight Tie Bars, Lane Ties.....	914.09
Strain Poles (Traffic Signal).....	921.05
Strain Pole Band Clamps	921.05A
Strand for Prestressed Concrete	905.07
Straw Mulch Blankets.....	917.14B
Structural Plate for Pipe (Corrugated)	Misc. #8
Structural Steel.....	906.04
Structural Tile.....	913.08
Structural Timber and Lumber	912.05
Structure Expansion Anchors	712.03K
Stud Shear Developers	906.09
Subbase.....	902
Sumps, Precast.....	913.07

-T-

Tackifiers for Mulch	917.14C
Tape, Lane Marking, Temporary	922.06A
Temporary Concrete Barriers	922.04
Temporary Overlay and Chip Seal Markers.....	922.06B
Temporary Seal for Cracks Injection	914.06
Temporary Signs.....	922.02
Tendons for Post Tensioning.....	905.08
Tension Wire.....	907.04B
Thermoplastic Pavement Marking	811.03D5, 811.03D6
Three Coat/Clear System, Post.....	907.03D
Tie Bar Grouting Systems	603.03B2
Tie Bars for Longitudinal Sawed Joints.....	914.09
Tile, Structural.....	913.08
Timber and Lumber, Structural.....	912.05
Timber Piling	912.06
Tower Lighting Units.....	918.10A
Traffic Cones.....	922.03A
Traffic Loop Sealant	921.08B
Treated Wood	912.05
Truss, Sign Support.....	919.08
Tube Railing, Galvanized	908.09B
Turbidity Curtain.....	916.07

-U-

Underdrain Outlet Endings	404.02C
Underdrain Pipe	909.07A, B, C

-V-

Vests.....	922.11
------------	--------

-W-

Wall Joint Drain, Geocomposite	910.05A
Warning Flashers and Lights.....	922.07B
Washers, Reflectorized	908.13
Water	911
Water Main Materials	923

Water Reducing/Retarding Admixture	903.02
Water Repellent, Penetrating Sealer	706.03S
Waterproofing Membrane, Preformed	914.11
Waterproofing Primer, Liquid Asphalt, RC 250	904.03B
Waterstop (Metallic)	908.07, 908.08
Watertight Joints	909.03
Weed Spray (Herbicides)	917.15
Welded Wire Reinforcement (Mesh)	905.06
Wet Reflective Optics.....	920.02C
Wire, Electrical Cable	918.03
Wire, High Tensile Fence	907.05A
Wire, Rope	908.11B
Wire Mesh.....	905.06
Wood Fence Posts.....	912.07B
Wood Mulch/Chips	917.13
Wood Posts and Lath for Silt Fence	916.02
Wood Posts for Guardrail (Dimensioned Sawed)	912.08
Wood Posts for Signs.....	912.08, 919.05
Woven Wire Fence Materials	907.03
Wrap, Filter Fabric.....	910.03A

-X- -Y- -Z-

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
401.03E End Section Grate for Culverts	VI	-	-	-	See Standard Plans for Sizes.
401.03E Precast Concrete Headwalls	Gen Cert	-	-	-	24" or less. For larger than 24" construct per Section 706 of Standard Specifications.
404.02C Underdrain Outlet Endings	VI	-	-	-	See Standard Plans.
501.02 Asphalt, Release Agents	VI	-	-	-	
NOTE: Must be approved by the project engineer. No fuel or oil-based agents.					
502.02B Overband Crackfill	VI See Remark	-	-	-	Must be a Qualified Product (502.02B).
603.03B2 Adhesive Systems for Grouting Dowel Bars and Tie Bars for Full-Depth Concrete Pavement Repairs	VI See Remark	-	-	-	Must be a Qualified Product (603.03B2).
Note: Use for grouting to existing concrete in the same direction of traffic in the same lane as the repair. For grouting lane ties (deformed bars positioned transverse to the direction of traffic located between traffic lanes) select from Adhesive Anchor Systems for Structural Anchors and Lane Ties (712.03J).					
706.03K4 Expansion Joint Devices for Bridges	See Remark	-	-	-	See project plans for list of approved devices and details.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
706.03S Penetrating Water Repellent (Protective Coating for Concrete)	VI See Remark	-	-	-	Must be a Qualified Product (706.03S).
707.02 Bushings for Pins and Link Plates	VI See Remark	-	-	-	Must be a Qualified Product (707.02).
708.01 Structural Prestressed Concrete Construction	Fabrication Inspection	-	-	-	See Chapter 5 of the SFQM for Precast Concrete Beam Approved Supplier List. See subsection 2.2. of the SFQM for fabrication inspection procedure. See Special Instructions.
710.03D Waterproofing Shotcrete	VI	-	-	-	
712.03A1c Abrasive, Low Dusting	Gen Cert	-	-	-	See Section 715.02.
712.03D Epoxy Mastic	VI	-	-	-	
712.03J Adhesive Anchor Systems for Structural Anchors and Lane Ties	VI See Remark	-	-	-	Must be a Qualified Product (712.03J).

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
712.03K Structure Expansion Anchors (Mechanical Expansion Anchors)	VI See Remark	-	-	-	Must be a Qualified Product (712.03K). Pull-out testing is required see MQAP Manual Section 3.03.
712.03L Mechanical Reinforcement Splicing	VI See Remark	1 per project	2 splices	-	See Special Instructions. Must be a Qualified Product (712.03L).
712.03X Grout Under Masonry Plates	VI	-	-	-	
712.03Y Embedded Galvanic Anodes	VI See Remark	-	-	-	Must be a Qualified Product (712.03Y).
713.02B Sealant for Perimeter of Beam Repairs	VI See Remark	-	-	-	Must be a Qualified Product (713.02B).
715.02 Coating Systems for New Hanger Assemblies	VI See Remark	-	-	-	Must be a Qualified Product (915).
715.02 Abrasive, Low Dusting	VI See Remark	-	-	-	Must be a Qualified Product (715.02).

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
715.02 Abrasive, Steel Grit	VI	-	-	-	Verify uniform profile after blasting of 1 to 2.8 mils per SSPC.
716.02 Abrasive, Low Dusting	VI See Remark	-	-	-	See Section 715.02.
803.02B Detectable Warning Surfaces	VI See Remark	-	-	-	Must be a Qualified Product (803.02B).
804.01 Glare Screen	VI	-	-	-	Included in Concrete Spec.
808.03C Temporary Fence Materials	VI	-	-	-	
810.03O Bridge Sign Connections	Fabrication Inspection	-	-	-	See Chapter 5 of the SFQM for Steel Highway Structure Approved Suppliers List. See subsection 2.4 of the SFQM for fabrication inspection procedure.
811.03D1 Waterborne, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D1).
811.03D2 Low Temperature Waterborne, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D2).

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
811.03D3 Regular Dry Paint, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D3).
811.03D4 Cold Plastic Tape, Preformed Pavement Marking Material	VI See Remark	-	-	-	MQAP Manual Section 5.14. Must be a Qualified Product (811.03D4).
811.03D5 Thermoplastic Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D5).
811.03D5 Thermoplastic, Blocks Rumble Strips and Snowmobile Crossings	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D5).
811.03D6 Thermoplastic, Sprayable, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D6).
811.03D7 Polyurea, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D7).
811.03D8 Modified Epoxy, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D8).

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
811.03D9 Preformed Thermoplastic, Preformed Pavement Marking Material	VI See Remark				MQAP Manual Section 5.14. Must be a Qualified Product (811.03D9).
901 Cement	Appr Mfr	See Remark	10 lb	45 ton	See Special Instructions, see MQAP Manual Section 2.06.
901.06 Slag Cement	Appr Mfr	-	10 lb	-	See Special Instructions for Cement.
901.07 Fly Ash, Pozzolanic Admixtures for Concrete	Appr Mfr	-	10 lb	-	See Special Instructions for Cement, see MQAP Manual Section 2.07

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
902 Coarse Aggregates	Test	See Remark	50 lb	100 ton	See Special Instructions Refer to Chapter 3 of the Procedures for Aggregate Inspection Manual for sampling information. See Current List of all Prequalified Aggregate Suppliers at Construction Field Services Web Page.
902 Dense-Graded Aggregates	Test	See Remark	50 lb	500 ton	
902 Open-Graded Aggregates	Test	See Remark	50 lb	100 ton	
902 Granular Material Class I	Test	See Remark	50 lb	100 ton	
902 Granular Material Class II (Subbase), Class IIA and Class IIAA	Test	See Remark	50 lb	500 cyd	
902 Class II (Abutment B. F.)	Test	See Remark	50 lb	100 cyd	
902 Granular Material Class III	Test	See Remark	50 lb	500 cyd	
902 Granular Material Class IIIA	Test	See Remark	25 lb	100 cyd	
902 Fine Aggregate	Test	See Remark	25 lb	100 ton	
902 Mineral Filler for HMA Mixtures	Test See Remark	1 per project	1 qt	10 ton	Refer to Section 902.11 of the 2020 Standard Specifications.
903.01 Air Entraining Admixtures	VI See Remark	-	-	-	Must be a Qualified Product (903.01).

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
903.02 Liquid Chemical Admixtures	VI See Remark	-	-	-	Must be a Qualified Product (903.02).
903.03 Latex Admixture for Concrete	Appr Mfr	1 per lot	1 qt	-	
903.04 Calcium Chloride Concrete Accelerators	VI See Remark	-	-	-	Note the chemical composition.
903.06 Membrane Curing Compound	Test Data Cert	1 per lot or batch	1 qt	200 gal	
NOTE: Curing compounds must not be used after ONE year from manufacture. Date of manufacture must be clearly printed on the outside of containers.					
903.07A Interim Curing (Linseed Oil Based)	Test Data Cert	1 per lot or batch	1 qt	50 gal	See Note for 903.06 above.
903.07C Insulating Blanket	Test Data Cert	-	-	10 sheets	
903.07D Polystyrene Insulation	Test Data Cert	-	-	-	
904.03A Asphalt Binder for HMA Mixtures	See Remark	See Remark	See Remark	-	See Special Instructions.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
904.03B Liquid Asphalt (MC)	Gen Cert	1 per batch	See Remark	-	1 gal from the top and 1 gal from the bottom of tank.
904.03B Liquid Asphalt (RC-250)	Gen Cert	1 per batch	2 qt	5 gal	
904.03C Emulsified Asphalt	Appr Mfr * See Remark	See Remark	See Remark	-	See Special Instructions.
905.03 Bar Reinforcement (Uncoated)	Appr Mfr *	1 per project per mfr per size	See Remark	500 lb	See Special Instructions.
905.03 Bar Reinforcement (Epoxy Coated) 1. Bar 2. Epoxy Coating Companies 3. Epoxy Coating Material (905.03C)	Appr Mfr * Appr Mfr * VI See Remark	1 per project per mfr per size	See Note	500 lb	See Special Instructions. Epoxy Coating must be a Qualified Product (905.03C).
905.03D Bar Chairs and Wire Ties for Epoxy Coated Steel Reinforcement	VI	-	-	-	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
905.06 Welded Steel Wire Reinforcement (Mesh)	Appr Mfr *	1 per project per mfr	See Remark	500 syd	See Special Instructions.
905.07 Strand for Prestressed Concrete	Appr Mfr *	1 per heat	2 pcs each 60 in long	-	See Special Instructions.
905.08 Tendons for Post Tensioning of Box Beams (Prestressing Strand)	Appr Mfr * See Remark	1 per heat	2 pcs each 60 in long	-	See Special Instructions.
905.08 Tendons for Post Tensioning of Box Beams (Post Tensioning Bar)	Test	1 per heat per project	2 pcs each 30 in long	-	
906.04 Structural Steel	Fabrication Inspection	-	-	-	See subsections 2.3 and 2.4 of the SFQM for bridge steel and structural steel fabrication inspection procedures, respectively. See Special Instructions.
906.05 Foundation Piles (Steel H Piling and Special Sections, Steel Shells for Cast-in-Place Concrete Piles and Pile Points)	Test Data Cert	-	-	-	
906.05 Pile Cutoffs	Gen Cert	-	-	-	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
906.06 Steel Piles (Temporary and Permanent Steel Sheet Piling)	Gen Cert	-	-	-	
906.07 High Strength Steel Bolts, Nuts, and Washers for Structural Joints	Test	1 per dia per length per lot per project	3 assemblies	-	See Special Instructions.
906.09 Shear Developers (Studs)	VI See Remark	-	-	-	Must be a Qualified Product (906.09).
907.03A – C Woven Wire Fence (Woven Wire Fabric, Barbed Wire, Smooth Line Wire)	Test Data Cert	1 per project per mfr	Full width of roll 5 ft 6 ft 4 ft	400 ft	
907.03D Woven Wire Fence (Steel Posts)	Test Data Cert	1 per project per mfr	1 post	25 posts	
907.03E Woven Wire Fence (Treated Wood Posts)	See Remark	-	-	-	See Section 912.07B.
907.03F Woven Wire Fence (Gates)	VI	-	-	-	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
907.04A Steel Chain Link Fence (Fabric)	Test Data Cert	See Remark	5 ft full width of roll	250 ft	1 per height and/or mesh size, per project and 1 per mfr per project.
907.04B Steel Chain Link Fence (Tension Wire)	Gen Cert	1 per project per mfr	3 ft	500 ft	
907.04C Steel Chain Link Fence (Post for Fence and Gates), (Pedestrian Fence and Structure Fencing (Steel))	Test Data Cert	1 per project per mfr	1 post	25 posts	See Special Instructions.
<p>Note: An alternative zinc/clear coat system will be allowed for pipe sections only. This alternative coating system shall comply with subsection 907.03D of the Standard Specifications for Construction.</p>					
907.04C Steel Chain Link Fence (Top Rail), ((Horz. Rail) (Pedestrian Fence))	Test Data Cert	1 per project per mfr See Remark	5 ft	250 ft	See Special Instructions.
907.04D & E Steel Chain Link Fence (Gates, Fence Fittings and Hardware)	VI	-	-	-	
907.05A High Tensile Wire Fence (Wire)	Test	1 per project per mfr	3 ft	250 ft	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
907.05B High Tensile Wire Fence (Treated Wood Posts)	See Remark	-	-	-	See Section 912.07B.
907.05C High Tensile Wire Fence (Hardware)	VI	-	-	-	
907.06 Protective Fence	VI	-	-	-	
908 Castings, Manhole 908.03 Malleable Iron 908.04 Steel 908.05 Gray/Ductile Iron	VI	-	-	-	
908.07 Sheet Lead	Gen Cert	-	-	25 sft	
908.08 Sheet Copper	Gen Cert	1 per consignment	13 in square or equivalent area	25 sft	May be accepted in field if weight requirements can be documented.
908.09A Tubing, Steel Railings (Base Plate, Angle, and Non-Tubular Post Elements)	Fabrication Inspection	-	-	-	See subsection 2.4 of the SFQM for fabrication inspection procedure.
908.09B Tubing, Steel Railings (Rail Elements and Tubular Post Elements)	Fabrication Inspection	-	-	-	See subsection 2.4 of the SFQM for fabrication inspection procedure.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
908.09C Tubing, Steel Railings (Hardware)	Test	1 per lot per diameter per project	1 assembly	-	See Special Instructions.
908.10 Hardware for Timber Construction	VI	-	-	-	
908.11A Guardrail, Steel Beam Elements, End Sections	Appr Mfr *	1 per project per mfr	1 piece at least 1 ft length	125 ft	Including Anchorage, Bridge, Shoes, Departing End Terminals.
908.11A Guardrail Approach Terminals	Appr Mfr *	-	-	-	
908.11B & C B. Hardware C. Steel Sleeves, Soil Plates, Bearing Plates, Backup Plates	VI	-	-	-	Item supplied by guardrail supplier.
908.11B Wire Rope	Gen Cert	-	-	-	
908.12 Steel Posts for Beam Guardrail	Appr Mfr *	1 per 1000 posts or fraction thereof	1 post	25 posts	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
908.13 Reflective Washers	VI See Remark	-	-	-	Inspect galvanizing, dimensions and type of sheeting.
908.14 Anchor Bolts, Nuts, and Washers	Test	1 per lot per diameter per project	1 assembly	-	See Special Instructions.
908.14D Anchor Bolts and Nuts for Other Purposes	Gen Cert	1 per lot per diameter per project	1 assembly	-	See Special Instructions.
909.01 Recycled Rubber Adjusting Rings for Manholes and Drainage Castings	VI See Remark	-	-	-	Must be a Qualified Product (909.01).
909.03 Watertight Joint Systems	VI See Remark	-	-	-	Must be a Qualified Product (909.03).
909.03 Gasket, Compression (O-Rings)	VI	-	-	-	Part of Watertight Joint System.
909.03 Gasket, External Rubber Type	VI	1 per lot or shipment	18 in length full width of gasket	-	Part of Watertight Joint System.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer* *	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.04A Reinforced Concrete Pipe	Appr Mfr *	1 percent of number of pcs of each size	See Remark	5 pieces of 42 in or smaller	See Special Instructions.
909.04B Reinforced Concrete Elliptical Pipe	Appr Mfr *	1 percent of number of pcs of each size	See Remark	5 pieces of 42 in or smaller	See Special Instructions.
909.04C Non-Reinforced Concrete Pipe	Appr Mfr *	See Remark	See Remark	10 pcs	See Special Instructions.
909.04D Precast Concrete Box Sections	Appr Mfr * See Remark	-	-	-	Spans 20 ft. and greater (measured from inside of exterior walls, parallel to the roadway centerline) require QA inspection. QA inspection may be required for spans from 10-20 ft. Box = 4 sided. See subsection 2.1 of the SFQM for fabrication inspection procedure. See Special Instructions.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.04E Precast Concrete End Section for Culverts and Sewers	Appr Mfr *	1 percent of number of pcs	Full size units	10 pcs	Strength test by coring or cylinders, VI dimensions and conditions. Test for air content. .
909.04G Precast Concrete Three-Sided or Arch Culverts	Appr Mfr See Remark	-	-	-	Spans 20 ft. and greater (measured from inside of exterior walls, parallel to the roadway centerline) require QA inspection. QA inspection may be required for spans from 10-20 ft. See subsection 2.1 of the SFQM for fabrication inspection procedure. See Special Instructions.
909.05A Corrugated Steel Pipe	Appr Mfr *	See Remark	See Remark	-	See Special Instructions.
909.05A1 Corrugated Steel Sheets (Galvanized)	Gen Cert	See Remark	See Remark	-	See Special Instructions.
909.05A1 Polymer Coating, Galvanized Corrugated Steel Pipe	VI See Remark	-	-	-	Coating must be from Qualified Products List (909.05A1).
909.05A3 Coupling Bands	Gen Cert	-	-	5 pcs	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.05B Corrugated Aluminum Alloy Sheet	Gen Cert	See Remark	See Remark	25 sheets	See Special Instructions.
909.05B Corrugated Aluminum Alloy Pipe	Gen Cert	1 per 1000 ft	See Remark	250 ft	Sample Size: A 6 in by 3 in (minimum) section cut from the end of the pipe avoiding the seams. Do not damage coating.
909.05C Steel End Section	Gen Cert	-	-	4 pcs	
909.05D 1. Steel Pipe (Jacked-in-Place)	Gen Cert	-	-	-	For drainage applications.
909.05D 2. Casing, Steel Pipe	VI	-	-	-	For drainage applications.
909.06 1. Corrugated Polyethylene Pipe (CPE/HDPE), (Smooth Lined Type S)	Appr. Mfr*	See Remark	See Remark	100 ft	See MQAP Chapter 3.10.
909.06 2. Corrugated Polyvinyl Chloride (CPV) Pipe	Test	1 per 1000 ft	See Remark	12 in. dia and over, 100 ft	Over 12 in. dia- one 10 ft and one 6 ft. length plus coupling.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.06 3. Plastic Pipe Class A, B and F Bury (CPE/HDPE & CPV)	VI See Remark	-	-	-	Must be a Qualified Product (909.06).
909.06 4. Smooth Polyvinyl Chloride (PVC) Pipe and Fittings for Sanitary Sewer	VI	1 per 6000 ft	1 piece, 5 ft in length	-	Sample must include bell end of pipe.
909.07A Pipe for Underdrains Smooth Perforated Plastic Pipe (PVC)	Test	1 per 2500 ft or fraction thereof	5 ft length	250 ft	Sample must include bell end of pipe.
909.07A1 Pipe for Underdrains Acrylonitrile-Butadiene-Styrene (ABS)	Test	1 per 6000 ft	1 piece, 6 ft in length	600 ft	If bell and spigot joint, sample from bell end.
909.07B Pipe for Underdrains Corrugated Plastic Tubing (Perforated and Non-Perforated) (Wrapped and Non-Wrapped)	Appr Mfr * 4-, 6-, or 8-in dia	1 per 5000 ft sample from coils	See Remark	250 ft	Sample Size, one 12 ft length plus coupling. For perforated tubing wrapped in fabric, tie fabric securely in place before cutting sample. Do not disturb fabric after cutting.
909.07C Outlet Pipe for Underdrains 1. Polyvinyl Chloride (PVC) Pipe	Test	1 per 2500 ft or fraction thereof	5 ft length	250 ft	See 404.02C for Underdrain Outlet Endings. Sample must include bell end of pipe.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.07C Outlet Pipe for Underdrains 2. Corrugated Steel Pipe	Appr Mfr *	See Remark	See Remark	-	See Special Instructions for 909.05A,. See 404.02C for Underdrain Outlet Endings.
909.07C Outlet Pipe for Underdrains 3. Corrugated Aluminum Alloy Pipe	Gen Cert	1 per 1000 ft	6 in x 3 in	250 ft	See 404.02C for Underdrain Outlet Endings. See 909.05B.
909.08A Bridge Deck Downspouts	VI	-	-	-	
909.08B Culvert, Downspouts 1. Corrugated Steel Pipe	Appr Mfr *	See Remark	See Remark	-	See 909.05A Corrugated Steel Pipe.
909.08B Culvert, Downspouts 2. Corrugated Aluminum Alloy Pipe	Gen Cert	1 per 1000 ft	6 in x 3 in	250 ft	See 909.05B.
909.08B Culvert, Downspouts 3. Corrugated Polyethylene Pipe (Corrugated Type C) (CPE/HDPE)	Test	1 per 1000 ft	See Remark	<12 in. dia up to 250 ft ≥12 in. dia up to 100 ft	A sample consists of one 10-foot-long piece, one 6-foot-long piece, and one coupling.
909.08C Bridge Deck Drain Extensions (Polyethylene)	Gen Cert	-	-	-	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.09 Cold Applied Pipe Joint Sealer (Mastic)	VI	1 per shipment from a single container	1 qt	-	
909.10 Drainage Marker Post	See Delineator Posts	-	-	-	
910.03A Geotextile Blanket (incl. Filter Bags)	Test	See Remark	See Remark	See Remark	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.
910.03A Knitted Sock Pipe Wrap	See Remark	-	-	-	See 909.07B Certified with Corrugated Plastic Tubing.
910.03B Geotextile Liner (Rip-Rap, etc.)	Test	See Remark	See Remark	See Remark	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.
910.03B Heavy Geotextile Liner (Rip-Rap, etc.)	Test	See Remark	See Remark	See Remark	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
910.03C Geotextile Separator (Woven, Non-woven)	Test	See Remark	See Remark	See Remark	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.
910.03D Stabilization Geotextile (Woven, Non-woven)	Test	See Remark	See Remark	See Remark	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.
910.04 Silt Fence Geotextile (fabric only)	VI See Remark	-	-	-	Must be a Qualified Product (910.04). See 916.02 for sampling and acceptance instructions for Silt Fence (full assembly).
910.05A Wall Drain	Test	1 per 2000 ft or less	See Remark	250 sft	See Special Instruction 910.05. Suppliers must provide separate samples of filter wrap geotextile and polymer core.
910.06 Road Grade Biaxial Geogrid	Test	1 per lot per shipment	1 pc 6 ft long full roll width	-	Sample must be rolled not folded. Include lot number and/or roll number, name of manufacturer, and the product or style number. Anticipate up to 28 calendar days for the testing of geogrid samples.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
911 Water	Test See Remark	1 per source	1 qt	-	Water approved for drinking by the Michigan Dept of Public Health may be used without sampling and testing.
912.05 Structural Timber and Lumber	Appr Mfr *	Each Charge	22 cores See Remark	-	48 cores if treatment is creosote.
912.06 Timber Piles	VI	-	-	-	
912.07B Treated Wood; Fence Posts, Guide Posts, Guard Posts and Mail Box Posts	VI	-	-	-	
912.08 Wood Posts and Blocks for Guardrail and Highway Signs (Dimension Sawed)	Appr Mfr *	Each Charge	22 cores	-	Cedar post need not be treated.
912.08Q Recycled Plastic or Rubber Guardrail Offset Blocks	VI See Remark	-	-	-	Must be a Qualified Product. May only be used on Steel Posts (912.08Q).
912.09 Timber for Rustic Construction	Gen Cert	-	-	-	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
913.03 Clay and Sand Lime Brick and Block	Test	1 per 250,000 or fraction thereof	6 pcs	1000 pcs	
913.03C Concrete Brick	Test Data Cert	See Remark	6 pcs	1000 pcs	1 from each 10,000 bricks or fraction thereof; 2 from lots more than 10,000 to 100,000; 3 from each lot over 100,000.
913.05 Concrete Block	Test Data Cert	See Remark	4 pcs	1000 pcs	One from lot of 10,000 or fraction thereof; 2 from lots more than 10,000.
913.06 Precast Reinforced Concrete Units for Drainage Structures (Tops, Risers and Sump Bases)	Appr Mfr *	1 percent per size	See Remark	10 pcs total	Submit QA cylinder test results and core samples. Submit sample 1-3 sq.in. from wall of unit if absorption is required.
913.06 Precast Drainage Structure Adjusting Rings	Gen Cert	-	-	-	
913.07 Precast Concrete Bases, for Drainage Structures	Appr Mfr *	5 percent of total	-	10 pcs total	
913.08 Structural Tile	Test	1 per proj.	6 tiles	1000 tiles	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
913.09 Slope Pavement Blocks	Appr Mfr *	1 per 25,000	6 blocks	1000 pcs	
914.03 Bituminized Fiber Joint Filler	Test Data Cert	1 per 1000 sft or fraction thereof	2 ft See Remark	150 sft	Sample for structure to be at least 5 in. wide. ¼ in. filler need not be sampled.
914.03B Recycled Rubber Joint Filler	VI See Remark	-	-	-	Must be a Qualified Product (914.03B).
914.03C Closed-Cell Polypropylene Foam	Test Data Cert	1 per 1000 sft or fraction thereof	2 ft See Remark	150 sft	Sample for structure to be at least 5 in. wide. ¼ in. filler need not be sampled.
914.04A Hot-Poured Joint and Crack Sealant	VI See Remark	-	-	-	Must be a Qualified Product (914.04A).
914.04B Backer Rod for Use with Hot-Poured Joint Sealant	VI	-	-	-	
914.05 Joint Spall Repair Materials	See Remark	-	-	-	See contract documents as applicable.
914.06 Epoxy Resin Adhesive and Temporary Seal (Crack Injection)	VI See Remark	-	-	-	Must be a Qualified Product (914.06).

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
914.07 Transverse Pavement Joints 1. Dowel Bars	Appr Mfr	-	1 bar	1200 bars	Bond Release Agent must be a Qualified Product (914.07A). See Special Instructions 914.07. Field Inspection required, MQAP Manual Section 3.04. See Special Instructions 914.07.
2. Dowel Baskets (Load Transfer Assemblies)	Appr Mfr	-	Full size unit	100 assemblies	
914.07A Coatings for Dowel Bars 1. Epoxy Coating Companies	Appr Mfr *	1 per project per mfr	1 bar	240 bars	Epoxy Coating must be a Qualified Product (914.07A2). Must be a Qualified Product (914.07A3).
2. Epoxy Coating Material	VI See Remark	-	-	-	
3. Bond Release a. Bituminous Material b. Alternate Bond Release Agents	Gen Cert VI See Remark	- -	- -	20 gal max -	
914.07C Dowel Bar Expansion Caps	VI	-	-	-	Caps must conform to Standard Plan R-40 Series.
914.08 End-of-Pour Joint Devices	VI	-	-	-	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
914.08 Deformed Bars 1. Bars 2. Epoxy Coating	Appr Mfr * VI See Remark	1 per project per mfr	-	500 lb	Epoxy Coating must be Qualified Product (905.03C).
914.09 Straight and Bent Tie Bars for Longitudinal Pavement Joints (Lane Ties) 1. Bars 2. Epoxy Coating	Appr Mfr * VI See Remark	1 per project per mfr	2 bar	500 lb	Epoxy Coating must be a Qualified Product (905.03C).
914.10 Bolts for Structure Expansion Anchors	Gen Cert	-	-	-	
914.11 Preformed Waterproofing Membrane and Joint Waterproofing Membrane	VI See Remark	-	-	-	Must be a Qualified Product (914.11). Do not use on Treated Wood Materials.
914.12A Elastomeric Bearings	Gen Cert	-	-	-	
914.12B Elastomeric Leveling Pads	Gen Cert	-	-	-	
915 Bridge Coating Systems	VI See Remark	-	-	-	Must be a Qualified Product (915).

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
916.01A Cobblestone	VI	-	-	-	
916.01C Riprap	VI	-	-	-	
916.02 Silt Fence (full assembly) Note: Sample to include identifying markings of fabricator. Indicate on sample ID description of markings. Note where markings were found.	Appr Mfr *	See Remark	See Remark	500 ft	1 sample for the first 3000 ft or fraction thereof; 1 sample for each additional 10,000 ft or fraction thereof; 1 piece 12 ft long by full fence height include 2 attached posts and lath. See 910.04 for acceptance instructions for Silt Fence Geotextile (fabric only).
916.07 Turbidity Curtain	VI				
917.03 Nursery Stock	VI	-	-	-	
917.04 Balling Material	VI	-	-	-	
917.05A Wire for Bracing and Guying	VI	-	-	-	
917.05B Hose for Bracing and Guying	VI	-	-	-	
917.05C Stakes for Bracing and Guying	VI	-	-	-	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
917.07 Compost	VI	-	-	-	
917.09 Chemical Fertilizer for Grass Seed	VI See Remark	-	-	-	Provide the bag label, showing the guaranteed analysis.
917.11 Grass Seeding Mixtures Grass Seed Varieties	VI See Remarks VI See Remark	1 per lot per shipment	1/2 lb	1100 lbs	For projects that include more than 5 acres of seeding, see Grass Seed Testing Special Provision in contract. Varieties of seed must be Qualified Product (917.11).
917.12 Sod	VI	-	-	-	
917.12A Pegs for Sodding	VI	-	-	-	
917.13 Mulching Materials for Nursery Stock	VI	-	-	-	Only shredded hardwood, wood chips or wood products not allowed.
917.14B1 & 2 High Velocity Mulch Blankets and Standard Mulch Blanket	VI See Remark	-	-	-	Must be a Qualified Product (917.14B 1 & 2). High velocity - netting 2 sides. Standard - netting 1 side.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
917.14C Mulch Anchoring - Latex, Recycled Newsprint, Wood Fiber, Guar Gum, Other Tackifiers	VI See Remark	-	-	-	Must be a Qualified Product (917.14C).
917.15 Weed Control (Herbicides)	Test Data Cert	-	-	-	
918.01 Flexible Metal Conduit	VI	-	-	-	
918.01A Electrical Conduit, Rigid (Galvanized Steel)	Gen Cert	See Remark	6 ft, include coupling, if applicable	400 ft	1 sample for 2500 ft or fraction thereof; 2 samples over 2500 to 10,000 ft; 1 sample for each additional 10,000 ft.
918.01B & C Electrical Conduit (Polyvinyl Chloride) Schedule 40 and 80	Gen Cert	See Remark	6 ft sample w/ bell end incl coupling	400 ft	1 sample for 2500 ft or fraction thereof; 2 samples over 2500 to 10,000 ft; 1 sample for each additional 10,000 ft.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
918.01D & E Electrical Conduit (Polyethylene/HDPE) Schedule 40 and 80	Gen Cert	See Remark	See Remark	400 ft	1 sample for 2500 ft or fraction thereof; 2 samples over 2500 to 10,000 ft; 1 sample for each additional 10,000 ft; 6 ft plus a separate section consisting of 2-18 in. long pcs. connected by the joint.
918.01F Electrical Conduit (Rigid Fiberglass)	Gen Cert	See Remark	6 ft sample w/ bell end incl. coupling	400 ft	1 sample for 2500 ft or fraction thereof; 2 samples over 2500 to 10,000 ft; 1 sample for each additional 10,000 ft.
918.02 Grounding System	VI	-	-	-	
918.02C Grounding Rods	VI	-	-	-	
918.03 Electrical Cable	Gen Cert	-	-	-	
918.06 Precast Concrete Handholes and Manholes for Electrical and Telephone Connections	Appr Mfr *	1 percent per size	-	10 pcs	
918.06D Light Weight Composite Handholes	VI See Remark	-	-	-	Must be a Qualified Product (918.06D).

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
918.08 Light Standards (Steel and Aluminum Light Standards)	Gen Cert	-	-	-	
918.08C Light Standards, Frangible Transformer Bases	VI See Remark	-	-	-	Must be a Qualified Product (918.08C).
918.09 Luminaries	Gen Cert	-	-	-	
918.10A Tower Lighting Units	Fabrication Inspection	-	-	-	See Chapter 5 of the SFQM for Steel Highway Structure Approved Supplier List. See subsection 2.4 of the SFQM for fabrication inspection procedure.
918.11A Guy Wire	Gen Cert	1 per size	3 ft	-	
919 Steel Sleeves for Wood Posts	Gen Cert	-	-	-	
919.02 Signs (Permanent)	See Remark	-	-	-	General Cert must be attached and inspected at project site.
919.02A1 Metal Sections (Extruded Aluminum)	VI See Remark	-	12 in. long and full width of section	-	Mill Cert must be submitted to the Project Engineer.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
919.02A2 Plywood	Gen Cert See Remark	-	-	-	Grade mark on materials serves as certification.
919.02A3 Aluminum Sheet	VI See Remark	-	Min. of 12 in. square	-	Mill Cert must be submitted to the Project Engineer.
919.02B1 Reflective Sheeting	VI See Remark	1 per run or lot	See Remark	1 roll, for less than 3 in. in width	Must be a Qualified Product (919.02B1) 4 pcs each 12 in. square. For rolls less than 12 in. width, at least 7.5 ft.
919.02C Sign Hardware	Gen Cert See Remark	-	-	-	Identifying marks on items may serve as certification.
919.03A Delineators, Aluminum Reflectors	Gen Cert	1 per shipment per color	21 pcs	25 pcs each color	
919.03B Delineators, Reflective Sheeting Reflectors	Gen Cert	1 per shipment per color	2 pcs each color	25 pcs each color	
919.03D Delineator Posts, Steel	Gen Cert	1 per project per mfr	1 post	80 post	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
919.03D Delineator Posts, Plastic	VI See Remark	-	-	-	Must be a Qualified Product (919.03D).
919.04 Steel, Galvanized Sign Posts	Test Data Cert	1 per project per mfr	See Remark	20 posts	Sample 30 in. length min. length. Posts for temporary signs may be painted.
919.05 Wood Sign Posts	Appr Mfr *	Each charge	22 cores	20 posts	General Cert to Construction Field Services. See 912.08.
919.06 Steel Column Breakaway Sign Supports	VI	-	-	-	Mill Cert must be submitted to the Project Engineer.
919.07 Cantilever Sign Supports	Fabrication Inspection	-	-	-	See Chapter 5 of the SFQM for Steel Highway Structure Approved Supplier List. See subsection 2.4 of the SFQM for fabrication inspection procedure.
919.08 Truss Sign Supports	Fabrication Inspection	-	-	-	See Chapter 5 of the SFQM for Steel Highway Structure Approved Supplier List. See subsection 2.4 of the SFQM for fabrication inspection procedure.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
919.10 Casings for Cantilever Drilled Piles	Gen Cert	-	-	-	For Cantilever, Drilled Shaft, Strain Pole, etc. Foundations.
920.02B Standard Glass Beads	Gen Cert	1 from each lot	2 lb	500 lbs	
920.02C Wet Reflective Optics	VI See Remark	-	-	-	Must be a Qualified Product (920.02C).
921.02 Messenger Wire and Span Wire	Gen Cert	1 per size	3 ft	-	
921.03 Traffic Signals and Mounting Assemblies	Gen Cert	-	-	-	
921.05 Traffic Signal Strain Pole	Gen Cert	-	-	-	
921.05A Strain Pole Band Clamps	VI See Remark	-	-	-	Must be a Qualified Product (921.05A).
921.08B Traffic Loop Sealant	Gen Cert	2 from each lot	Tubes	-	
922.02 Temporary Traffic Control Temporary Signs	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.02B Temporary Traffic Control Reflective Sheeting (Signs)	See Remark	-	-	-	See MQAP Manual Section 3.07.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
922.02D Temporary Traffic Control Sign Covers	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.03 Temporary Traffic Control A. Cones B. Drums	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.03E Temporary Traffic Control Type III Barricade, Reflective Sheeting	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.04 Temporary Traffic Control Temporary Concrete Barriers (TCB)	Test Data Cert See Remark	Each project	-	-	Contractor must provide certifications and documentation confirming the TCB provided meets the requirements of subsection 922.04.A of the Standard Specifications for Construction.
922.04A Barrier Reflectors Temporary	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.04A Barrier Reflectors Permanent	VI	-	-	-	

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
922.06A Temporary Traffic Control Temporary Pavement Markings; Type R and NR Tape	VI See Remark	-	-	-	Must be a Qualified Product (922.06A).
922.06A2 Temporary Traffic Control Temporary Pavement Markings; Paint	VI See Remark	-	-	-	Must be a Qualified Product (811.03D).
922.06B Temporary Traffic Control Temporary Raised Pavement Markers	VI See Remark	-	-	-	Must be a Qualified Product (922.06B).
922.06C Temporary Traffic Control Pavement Marking Cover	VI See Remark	-	-	-	Must be a Qualified Product (922.06C).
922.07A Temporary Traffic Control Lighted Arrows; Type B and C (Solar Assist)	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.07B Temporary Traffic Control Warning Flashers and Lights; Type A, B, C	See Remark	Each project	3 each type	-	See MQAP Manual Section 3.07.
922.07C Temporary Traffic Control Portable Changeable Message Signs	See Remark	-	-	-	See MQAP Manual Section 3.07.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
922.11 Temporary Traffic Control Sign Paddles and Vests	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.12A Temporary Traffic Control Dust Palliative 1. Calcium Chloride Solids	Test Data Cert	1 per project	5 lb	5000 lb	
922.12A Temporary Traffic Control Dust Palliative 2. Calcium Chloride Solutions	Test Data Cert	1 per project	1 qt	1000 gal	
923 Watermain Materials	Gen Cert	-	-	250 ft of pipe	See contract documents as applicable.
1005.02A Standard Mortar and Grout Mixtures	VI	-	-	-	
1005.02B Non-Shrinking Mortar and Grout, Type H-1(Non-Metallic) Pre-Mixed	VI See Remark	-	-	-	Must be a Qualified Product (1005.02B).
1005.02C Admixture for Expansive Grout, Type E-1	Test Data Cert	-	-	-	
Note: Certification to include manufacturers recommended dosage per sack of cement.					
1006 Prepackaged Hydraulic Fast Set Mortar	VI See Remark	-	-	-	Must be a Qualified Product (1006).

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer*	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
Misc. #2 Culvert, Cast and Ductile Iron	Gen Cert	-	-	250 ft	
Misc. #3 Clay Pipe	Gen Cert	See Remark	See Remark	10 pieces	See Special Instructions.
Misc. #5 Galvanized Slotted Drain Pipe	VI See Remark	-	-	-	MDOT approval of Design is required. Coating thickness checked at project site.
Misc. #8 Corrugated Galvanized Steel Structural Plated	Gen Cert	1 per 100 plates or fraction thereof	1 piece at least 3 in. by 3 in.	10 plates	
Misc. #9 Aluminum Alloy Structural Plates	Gen Cert	-	-	-	
Misc. #13 Pavement Warning Strips	VI	-	-	-	
Misc. #14 Bituminized Cotton Fabric and Fiberglass Fabric	Gen Cert	See Remark	1 piece full width of roll, min of 3 ft	5 rolls	1 per 100 rolls (50 sft per roll) or fraction thereof; for lots of more than 100 rolls - 1 sample plus 1 for each 500 rolls or fraction thereof. Do not sample from first 3-4 ft of roll.

***** See following pages for Special Instructions *****

Special Instructions

708.01 Prestressed Concrete

Fabrication inspection is required for all prestressed miscellaneous bridge products, prestressed straight-strand bridge beams, and prestressed deflected-strand bridge beams. The following steel components incorporated into prestressed concrete beams do not require fabrication inspection: dowel bars and sole plates.

712.03L Mechanical Reinforcement Splicing

The contractor must make test splices, witnessed by the Engineer, on the largest bar sizes that are to be spliced. Test splice consists of 2 pieces of reinforcing bar joined by the coupler with 12 inches of bar exposed on each end of the coupler.

901 Cements and Fly Ash

Samples of fly ash and slag cement must be accompanied by a sample of the Portland cement with which it is being used. The plastic lined cement sample bags furnished by the laboratory will hold 10 pounds when full.

902 Prequalified Aggregate Suppliers

Quality Assurance tests will be conducted by Department personnel at the frequencies stated in Chapter 3 of the MDOT Aggregate Supplier Program, found in the Procedures for Aggregate Inspection Manual.

904.03A Asphalt Binder for HMA Mixtures

If the Asphalt Binder is supplied from a source currently on the Approved Asphalt Binder Certifier List, a certification meeting the requirements of Section 2.04.05 of the Materials Quality Assurance Procedures Manual is required. See the contract documents for sampling, acceptance, and daily monitoring requirements.

If the binder is supplied from a source that is not currently shown in the Approved Asphalt Binder Certifier List, the asphalt binder must be sampled, tested, and approved for use prior to incorporation into the project. See contract documents for sampling, acceptance, and monitoring requirements.

See Current List of Asphalt Binder Certifiers at Construction Field Services Web Page.

Instructions to Construction Field Services web page: From MDOT home page (michigan.gov/mdot), click on about MDOT (left side), then click on Highway Field Services, and then click Construction Field Services. The Approved Asphalt Binder Certifier List is under Resources & Publications.

Actual Current List of Approved Asphalt Binder Certifier web page address:
http://michigan.gov/documents/AppBinderCertlist_49824_7.pdf

904.03C Emulsified Asphalt

Size of Sample – For CV Sampling see Section 2.05.06 of the Materials Quality Assurance Procedures Manual. For all other sampling see contract documents for criteria. Submit the samples in plastic containers only.

905.03 Bar Reinforcement (Uncoated)

Sample size must be 2 pieces, one 24 in. and one 36 in. Sample ID must include the name of the bar manufacturer, lot number, and heat number. Mill Cert must be attached to the Sample ID form.

905.03C Bar Reinforcement (Epoxy Coated)

Sample size must be 2 pieces, one 24 in. and one 36 in. Sample ID must include the name of the epoxy coating company, epoxy resin trade name, name of bar manufacturer, lot number, and heat number. Mill Cert must be attached to the Sample ID form. Epoxy coating must be a Qualified Product (905.03C).

905.06 Welded Steel Wire Reinforcement

Sample size must be one-piece, full width of fabric with two transverse wires. Longitudinal wires must extend 6 in. to 8 in. either side of transverse wires. Sampling not required when larger wire is less than 0.13 in. (w1.5) in dia. Include on sample ID the size that the wires are supposed to be. Sample may be folded or cut into approx. 3 ft. sections. If cut, pieces should be wired together and identified. Mill Cert must be attached to the Sample ID form.

905.07 Strand for Prestressed Concrete

Do not obtain sample from within 5 feet of the end of the reel. Mill Cert must be attached to the Sample ID form.

905.08 Tendons for Post Tensioning of Box Beams – Prestressing Strand

Do not obtain sample from within 5 feet of the end of the reel. Mill Cert must be attached to the Sample ID form.

906.04 Structural Steel

Fabrication inspection is required for all main and secondary bridge member pay items listed in 707.04.

Fabrication inspection is required for structural steel and pipe bridge railing pay items listed in 711.04.

Fabrication inspection is required for the following structural steel bridge rehabilitation pay items listed in 713.04: pin and hanger replacement, bearing stiffeners at temporary supports, retrofit structural steel, and structural steel welded repairs.

The following structural steel components do not require fabrication inspection: plate washers and pier nosing.

906.07 High Strength Steel Bolts

An assembly is typically a combination of a bolt, nut, and washer but may be any combination of a bolt, nut, washer, lock washer, etc. depending on the project specifications. Mill Certs must be included for each component of the assembly and be attached to the Sample ID form. Plate washers are not required to be sampled and tested.

907.04C Steel Chain Link Fence-Posts for Fence and Gates

An alternative zinc/clear coat system will be allowed for pipe sections only. This alternative coating system shall comply with subsection 907.03D of the Standard Specifications for Construction.

907.04C Steel Chain Link Fence-Top Rail, Horizontal Rail

An alternative zinc/clear coat system will be allowed for pipe sections only. This alternative coating system shall comply with subsection 907.03D of the Standard Specifications for Construction.

908.09C Tubing, Steel Railings (Hardware)

An assembly is typically a combination of a bolt, nut, and washer but may be any combination of a bolt, nut, washer, lock washer, etc. depending on the project specifications. Plate washers are not required to be sampled and tested.

908.14 Anchor Bolts, Nuts, and Washers

An assembly is typically a combination of a bolt, nut, and washer but may be any combination of a bolt, nut, washer, lock washer, etc. depending on the project specifications. For Type C, D, E and J cantilevers, the sampling frequency is 1 assembly per heat, per diameter, per foundation, for a max of 3 per project. Full length bolts are required for testing but if the total length is less than 20", a second sample must be submitted for testing. Non MDOT

standard plan bolts require shop drawings along with a Mill Cert attached to the Sample ID form. Stainless steel anchor bolts are not required to be sampled and tested. Plate washers are not required to be sampled and tested.

908.14D Anchor Bolts and Nuts for Other Purposes

A General Cert is acceptable for stainless steel anchor bolts, pedestal foundations for pedestrian signals, push buttons, controller cabinets, and Hawk signals and repeaters. Anchor bolts for all other purposes require testing. An assembly is typically a combination of a bolt, nut, and washer but may be any combination of a bolt, nut, washer, lock washer, etc. depending on the project specifications. Plate washers are not required to be sampled and tested.

909.04A Reinforced Concrete Pipe

909.04B

Size of Sample - Full size units for strength test. For absorption tests, 26-inch square to 81-inch square in area from the wall of each piece of pipe tested.

Number of Samples - One percent of the number of pieces of each size.

Reinforced concrete pipe 42-inch diameter and larger may be tested by coring. Size of core will be 4-inch nominal diameter (but not less than 3 ¼ inches actual). Up to 1 percent of the number of pieces of pipe for each size, but not less than 3 pieces, will be selected for coring. One core will be drilled and tested from each of these test pieces. Reinforcement will be inspected prior to incorporation in the pipe.

909.04C Nonreinforced Concrete Pipe

Size of Sample - Same as reinforced concrete pipe.

Number of Samples - One percent of the number of pieces, but not less than 2 pieces of each size except that at the option of the department the following sampling schedule will apply for 4 inches through 24 inches in diameter sewer pipe for quantities of 500 or more:

Sampling Schedule - Per the following:

Concrete Pipe	Number of Samples
500 to 1,000 pieces	6
1,001 to 2,000 pieces	8
2,001 to 5,000 pieces	11
Over 5,000 pieces thereof	2 samples per 1,000 or fraction

909.04D Precast Concrete Box Sections

The following structural steel components do not require fabrication inspection: plate washers, connection plates, and connection angles used to connect culvert segment, headwall, and wingwall.

909.04G Precast Concrete Three-Sided or Arch Culverts

The following structural steel components do not require fabrication inspection: plate washers, connection plates, and connection angles used to connect culvert segment, headwall, and wingwall.

909.05A Corrugated Steel Pipe

Size of Sample - A 6-inch by 3-inch (minimum) section cut from the pipe. The sample should be taken from the end of the pipe avoiding the seams. Care should be taken to assure the coating is not damaged during sampling. Mill Cert must be attached to the Sample ID form.

Number of Samples - Per the following:

Diameter of Pipe	Quantity Represented (maximum)
12 inches or less	2500 ft
15 inches through 54 inches	1000 ft
60 inches and over	500 ft

Less than 5 percent of the quantity in the above table may be visually inspected.

909.05A1 Corrugated Galvanized Steel Sheets

Size of Sample - One strip the full width of the sheet and 3 ½ inches in the direction of the length of the sheet. The strip may be cut from the end of the sheet for material coated in coils. If the sheets were individually coated after being cut to length, as indicated by heavy accumulations of zinc at one end, the sample strip shall be cut from the end opposite the heavy accumulation and after cutting 4 inches from the end of the sheet. Mill Cert must be attached to the Sample ID form.

Number of Samples - Per the following:

Diameter of Pipe Represented (max)	Length of Sheet	Quantity
12 inches or less	44 inches or less	2500 ft
15 through 54 inches	50 to 175 inches, approx*	1000 ft
60 inches and over	190 inches and over*	500 ft

*Larger pipe may be made from combination of shorter sheets. Less than 5 percent of the quantity in the table above may be visually inspected.

Note: Normally each heat and thickness is to be sampled. Exception may be made where quantities are limited and/or mixtures of heat numbers are excessive.

909.05B Corrugated Aluminum Alloy Sheets

Size of Sample - A transverse strip full width of the sheet and at least 3 inches in length cut from the end of the sheet.

Number of Samples - A sample shall be taken from each of 3 different sheets for lots weighing 5 tons or less, from 4 sheets for lots weighing more than 5 tons and less than 10 tons, and from 5 sheets for lots weighing 10 tons or more.

910.03 Geotextiles

Sampling Frequency - Obtain samples to represent the required quantity of geotextile according to the following schedule:

Geotextile	First Sample	Additional Samples
Blanket	500 to 1500 syd	7,500 syd or less
Liner for Riprap	500 to 1500 syd	5,000 syd or less
Separator/Stabilization	500 to 1500 syd	25,000 syd or less
Liner for Heavy Riprap	500 to 1500 syd	4,000 syd or less

Maximum for VI - 500 syd (4500 sq ft)

Size of Sample - Sample must be a minimum of 75 sft, taken across the full roll width. For rolls over 15 ft wide, sample must be a minimum of 5 ft long, taken across the full roll width.

Geotextile samples submitted for testing must be identified with the lot number and/or roll number, the name of the manufacturer, and the product or style number.

Notes:

Geotextiles must be unwrapped one full roll circumference prior to sampling.

Geotextiles must be rolled, not folded, and shipped in a manner to prevent creases in the fabric.

910.05 Drainage Geocomposites

Size of Sample –

Filter wrap geotextile sample must be a minimum of 75 sft, taken across the full roll width.

Polymer core sample must be a minimum of 6 ft long, taken across the full roll width.

Coupon of the assembled drainage geocomposite must be a minimum of 1 ft long, taken across the full roll width.

Notes:

Manufacturers and suppliers must provide separate samples of filter wrap geotextile and polymer core for testing. These samples must be taken from the same production lot as the assembled drainage geocomposite intended for use on the project.

Include a coupon of the assembled drainage geocomposite when the separate components are submitted for testing.

Assembled coupon and component samples of the drainage geocomposite submitted for testing must be identified with the lot number and/or roll number, the name of the manufacturer, and the product or style number.

914.07 Load Transfer Assemblies; Dowel Baskets

Field Inspection required per Chapter 3.04 of the Materials Quality Assurance Procedures Manual. A Powerpoint in Division 602 of the Construction Manual has been created to assist with the field inspections. Form #0553 is to be used to document the inspections.

Assemblies must meet the requirements of Standard Plan, R-40-I.

All shipments of load transfer assemblies will be accompanied by proper certification documentation.

- Certification from steel (dowel bar) manufacturer.
- Certification from epoxy coating company.
- Documentation of epoxy coating.
- Certification from assembly manufacturer.
- Documentation of bond release.

When shipment is made to a project, each bundle will bear a legible tag with the following information:

- Assembly manufacturer name and plant location.
- Control section/project number.
- Lot number or other identification that will also be shown on the accompanying certification.
- Supplier and/or contractor's name.

Misc. #3 Clay Pipe

Normal Sampling Frequency - One percent of the number of pieces, but not less than 2 pieces of each size except that at the option of the department the following sampling schedule will apply for 4-inch through 24-inch diameter sewer pipe for quantities of 500 or more:

Sampling Schedule - Per the following:

Clay Pipe	Number of Samples
500 to 1,000 pieces	6
1,001 to 2,000 pieces	8
2,001 to 5,000 pieces	11
Over 5,000 pieces thereof	2 samples per 1,000 or fraction thereof

Size of Sample - Full size units for strength test. For absorption tests, 26 inches square to 82 inches square in area from the wall of each piece of pipe tested.

Approved Suppliers

The firms listed in this section have received written permission from the Construction Field Services Division to recertify material for use on Michigan Department of Transportation projects. Supplying materials is also allowed by manufacturers listed in the Approved Manufacturers List.

When recertification of any materials is made by any firm not found on this list, please notify the Construction Field Services Division, Materials Control, immediately.

See also Section 2.02 of the Materials Quality Assurance Procedures Manual.

Approved Suppliers

A.J. Rehmus & Son, Inc., Bay City, MI
ABC Coating Co. of Illinois, Inc., Manteno, IL
ABC Coating Co. of Michigan, Inc., Wyoming, MI
ABC Coating Co. of Minnesota, Inc., Minneapolis, MN
ABC Coating Co. of Oklahoma, Inc., Tulsa, OK
Action Traffic & Maintenance Co., Flint, MI
ADL Systems, Inc., Portland, MI
Allied Seed, L.L.C., Nampa, ID
Alro Steel Corporation, Alpena, MI
Art Thureson, Inc., Waterford, MI
Austin Morgan Companies, Clarkston, MI
B&R Reinforcing, Columbus, OH
BARNSCO, Detroit, MI
Bella Concrete Construction, LLC, Houghton Lake, MI
Boomer Construction Materials, Detroit, MI
Brandt Technologies LLC, Bensenville, IL
Burt Forest Products Co., Ann Arbor, MI
C & D Hughes, Inc., Charlotte, MI
C.A. Hull Co., Inc., Walled Lake, MI
Cadillac Culvert, Cadillac, MI
Carroll Distributing and Construction Supply, Inc. (Store 16), Wyoming, MI
Causie Contracting, Inc., Mason, MI
Central Michigan Contracting, Inc., Houghton Lake, MI
Chiles Michigan, Inc., Flat Rock, MI
Cipparrone Contracting, Inc., Southfield, MI
CMA Supply, South Bend, IN
Green Infrastructure Partners, Inc., Taylor, MI
Concrete Central Inc., Grand Rapids and Traverse City, MI
Core and Main LP, Canton, Kentwood and Shelby Twp., MI
Crawford Contracting, Inc., Mt. Pleasant, MI
CSI Geoturf, Inc., Highland, Traverse City, and Byron Center, MI
D.J. McQuestion & Sons, Inc., LeRoy, MI
Dale Dukes & Sons, Inc., Big Rapids, MI
Davis Construction, Lansing, MI
Dayton Superior Corporation, Miamisburg, OH, Oregon, IL, Valparaiso, IN
Diane Dukes, Inc., Big Rapids, MI
Doan Construction, Ypsilanti, MI
Dornbos Sign & Safety Inc., Charlotte, MI
Eastlund Concrete Construction, Holt, MI
East Jordan Iron Works, Inc., Wyoming, MI
Edward R. White Contractor, Inc., Waterford, MI
Elsey Construction Products, Harper Woods, MI
Environmental Protection Products, Williamsburg, MI
ERSCO Construction Supply, Lansing and Wyoming, MI
ETNA Supply Co., Chesterfield, Flint, Grand Ledge, Grand Rapids and Holland, MI
ETNA Supply Co., Jackson, Kalamazoo, Mt. Pleasant and Muskegon, MI
ETNA Supply Co., Saginaw, Sault Ste. Marie, Springfield, Traverse City and Wixom, MI
ETNA Supply Co., South Bend, IN and Toledo, OH
Evergreen Seed Supply, Lambertville, MI

Approved Suppliers

F&M Concrete Construction, LLC, Dimondale, MI
Ferguson Enterprises, Inc., Flushing, Kalamazoo, Kentwood, Lansing, and Warren, MI
Firelands Supply Co., Norwalk, OH
Fort Wayne Contracting, Inc., Detroit, MI
Frederick Steel Company, Cincinnati, OH
Future Fence Co., Sterling Heights, MI
G3 Steel Group, Troy, MI
Geo Products, Birmingham, MI
Give 'Em-A-Brake Safety, Grandville, MI
Grant Welding Service, Grant, MI
Harbor Pipe and Supply, Traverse City, MI
Harris Rebar/Ambassador Steel Corporation, Comstock Park and Lansing, MI,
Bourbonnais, IL
Harris Rebar, Bethlehem, PA
Harris Supply Solutions, Inc., Kokomo, IN
Hunt Brothers Concrete Contractors, Inc., Whittemore, MI
Hymmco, Saginaw, MI
Indiana Material Handling, IMH Products, Inc., Indianapolis, IN
InteRebar Fabricators/InteRebar Epoxy, Schererville, IN
J & J Contracting, Ithaca, MI
J & N Construction, LLC, Gaylord, MI
J.D. Russell Co., Utica, MI
JISI Group, LLC, Sterling Heights, MI
Jacklin Steel Supply Co., Escanaba, MI
Jensen Bridge and Supply Co., Grand Rapids and Sandusky, MI
John Deere Landscapes, Ann Arbor, and Grand Blanc, MI
John Deere Landscapes, Clinton and Commerce Townships, MI
John Deere Landscapes, Grand Rapids, Holland, and Kalamazoo, MI
John Deere Landscapes, Dimondale, Livonia, Madison Heights, and Saginaw, MI
John Deere Landscapes, Shelby Township
John Deere Landscapes, Taylor, and Traverse City, MI
Kalamazoo Forest Products, Inc., Otsego, MI
Kamminga & Roodvoets, Inc., Grand Rapids, MI
Kenmark, Inc., Buckley, MI
Klein Brothers Hardwood, Inc., Milford, MI
L.J. Construction, Inc., Clifford, MI
L.W. Lamb, Inc., Saugatuck, MI
Lane Enterprises, Inc., Carlisle, PA
Mack Industries, Inc., White Lake, MI
Manthei Development Corp., Charlevoix, MI
Martin J. Concrete, Inc., Coopersville, MI
Meadow Burke, Palisades Park, NJ
Metro Rebar, West Bloomfield, MI
Michigan Highway Signs, Flint, MI
Michigan Pipe and Valve, Jackson, Saginaw, and Traverse City, MI
Midway Contractor Supply, Negaunee, MI
Midwest Pipe Coatings, Schererville, IN
Milbocker & Sons, Inc., Allegan, MI
Miller Products & Supply Company, Iron Mountain, MI

Approved Suppliers

Nashville Construction Company, Nashville, MI
Nationwide Fence & Supply Co., Chesterfield, MI
North Coast Roofing Systems, Grand Rapids, MI
Northern Concrete Pipe, Bay City, Charlotte, Clarkston, and Wyoming, MI; Sylvania, OH
Northern Construction Services Corp., Niles, MI
NuTek Steel, Toledo, OH
OEM Distribution, LLC, Detroit, MI
Oglesby Construction, Inc., Norwalk, OH
One Supply Group, Auburn Hills, MI
P.K. Contracting, Inc., Lake City, MI
Peninsula Prestress Company, Clarksville, MI
Power Line Supply Company, Reed City, MI
Prestress Services Industries, LLC, Decatur, IN and Mount Vernon, OH
Rathco Safety Supply, Inc., Portage, MI
Remington Construction Company, Inc., Mattawan, MI
Rhino Seed and Landscape Supply, Bradley and Brighton, MI
Rightway Fence Co., Sterling Heights, MI
Sanches Construction Company, Lansing, MI
Simcote, Inc., Saint Paul, MN and Marion, OH
Snowden, Inc., Escanaba, MI
Standale Lumber, Grandville, MI
StressCrete Group, Atchison, KS
Striker Supply, Traverse City, MI
Sweeney Construction Materials, Novi, MI
T & D Concrete Construction LLC, Mason, MI
Titusville Fabricators, Inc., Franklin, PA
Tri-Valley Landscaping, Inc., Saginaw, MI
Upper Peninsula Concrete Pipe Co., Escanaba, MI
Van Laan Construction Supply, Dutton, MI
Wady Industries, Maquoketa, IA
Watson Bowman Acme Corp., Amherst, NY
Weyand Bros. Inc., Saginaw, MI

Approved Manufacturers

The materials in this section may be accepted for use on Michigan Department of Transportation projects on the basis of certification from the suppliers listed under specific materials.

This Approved Manufacturers List is in accordance with the 2020 Standard Specifications for Construction.

See also Section 2.02 of the Materials Quality Assurance Procedures Manual.

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Approved Distribution Facilities (not manufacturer specific)
901 Cement	<p>Argos USA, LLC - Martinsburg, WV</p> <p>Ash Grove - Mississauga, Ontario, Canada; Joliette, Quebec, Canada</p> <p>Buzzi Unicem USA - Chattanooga, TN; Festus MO; Greencastle, IN</p> <p>Central Plains Cement - Sugar Creek, MO</p> <p>Continental Cement Co. - Hannibal, MO</p> <p>Fairborn Cement Company – Fairborn (Xenia), OH</p> <p>Goltas Cement Company – Isparta, Turkey</p> <p>Holcim (US), Inc. - Alpena, MI; Paulding, OH; and Bloomsdale, MO</p> <p>Illinois Cement Co. - LaSalle, IL</p> <p>Kosmos Cement Co. - Louisville, KY (Type 1 Only)</p> <p>LeHigh Cement Co., LLC - Logansport and Mitchell, IN; Union Bridge, Maryland; Picton, Ontario, Canada</p> <p>McInnis Cement - Port Daniel-Gascons, Quebec, Canada</p> <p>St. Mary's Cement, Inc. (US) - Detroit and Charlevoix, MI; Bowmanville and St. Mary's, Ontario, Canada</p>	<p>Ash Grove - Detroit, and Dundee, MI; Duluth, MN</p> <p>Buzzi Unicem USA - Elmira and Grandville, MI; Elkhart, IN; Joliet, IL</p> <p>Holcim (US), Inc.- Detroit, Essexville, Muskegon, St. Joseph and Zilwaukee, MI; Chicago, Lemont and Summit, IL; Toledo, OH; Green Bay, WI</p> <p>St. Mary's Cement, Inc. (US) - Cleveland 1, Cleveland 2, Marysville and Toledo, OH; Ferrysburg, MI</p> <p>Sultan Cement, LLC – Warren, MI</p>
901.06 Slag Cement	<p>Ash Grove - Detroit, MI; Mississauga, Ontario, Canada</p> <p>Holcim (US), Inc. - South Chicago, IL</p> <p>Lehigh Cement Company, LLC – Middlebranch, OH</p> <p>Skyway Cement Company, LLC - Chicago, IL</p> <p>St. Mary's Cement, Inc. (US) - Detroit, MI; Milwaukee, WI</p>	<p>Ash Grove - Dundee, MI</p> <p>Holcim (US), Inc. - Detroit, Essexville, Muskegon, St. Joseph and Zilwaukee, MI; Chicago, Lemont and Summit, IL; Toledo, OH; Green Bay, WI</p> <p>St. Mary's Cement, Inc. (US) - Cleveland 1, Cleveland 2 and Marysville, OH; Ferrysburg, MI</p>

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Approved Distribution Facilities (not manufacturer specific)
901.07 Pozzolanic Admixtures (Fly Ash) for Concrete	<p>Ash Grove - Bell River, St. Clair, MI</p> <p>Boral Resources - Avon Power Plant, Avon Lake, OH; Erickson Power Plant, Lansing, MI; Sammis Power Station, Stratton, OH; Monroe Power Plant, Monroe, Michigan; Schahfer Station, Unit 15, Unit 17 & Unit 18, Wheatfield, IN; Labadie Power Station, Labadie, MO; Rush Island Power Station, Festus, MO; Coal Creek Steam Generating Plant, Underwood, ND</p> <p>Charah, Inc. - Zimmer Power Station, Moscow, OH; Miami Fort Unit 7 & 8, North Bend, OH</p> <p>Holcim (US), Inc. - Will Co. Plant, Romeoville, IL; Elm Road Generating Station, Oak Creek, IL; Columbia, Portage, WI; Edgewater Sta. Unit 5, Sheboygan, WI; Pleasant Prairie, Kenosha, WI; Weston #3, Wausau, WI</p> <p>Ozinga – Belle River Power Plant, East China, MI</p> <p>Separation Technologies, LLC - Clifty Creek Power Station, Madison, IN; Longview Power Plant, Maidsville, WV</p> <p>Waste Mgmt./FlyAsh Direct - Zimmer Power Plant, Moscow, OH; Miami Fort Unit 7 & 8, North Bend, OH; Avon Lake Unit 9, Cleveland, OH; Joppa Generating Station, Joppa, IL</p>	Ash Grove - Dundee, MI

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
903.03 Latex Admixture For Concrete	Trinseo BASF Corporation Polytherm Systems, Inc., General Tires	
904.03C Emulsified Asphalt	See Current List of Emulsified Asphalts at Construction Field Services Web Page. Instructions to Construction Field Services web page: From MDOT home page (michigan.gov/mdot), click on about MDOT (left side), then click on Highway Field Services, and then click Construction Field Services. The Approved Emulsified Asphalt Suppliers List is under Resources & Publications.	
905.03 Bar Reinforcement (Uncoated)	ABC Coating Co. of MI, Inc. ABC Coating Co. of IL, Inc. ASI Alton Steel, Inc. Byer Steel (formerly A.B. Steel) CMC Steel CMC Steel Florida CMC New Jersey CMC Steel Oklahoma CMC Tennessee CMC Steel Texas CMC Steel Cascade Steel Rolling Mills ERSCO Construction Supply EVRAZ Rocky Mountain Steel Gerdau Ameristeel Corporation Charlotte Steel Mill Div. Jackson Steel Mill Div. Midlothian Steel Mill Div. St. Paul Steel Mill Div. HYMMCO, LLC Nucor Steel Nucor Steel Auburn, Inc. Nucor Steel Birmingham, Inc. Nucor Steel Connecticut, Inc Nucor Steel Jackson, Inc. Nucor Steel Kankakee, Inc. Nucor Steel Marion, Inc. Nucor Steel Sedalia, LLC Optimus Steel, LLC Steel Dynamics Inc.	Wyoming, MI Manteno, IL Alton, IL Cincinnati, OH Baldwin, FL Sayreville, NJ Durant, OK Knoxville, TN Seguin, TX Cayce, Columbia, SC McMinnville, OR Lansing and Wyoming, MI Pueblo, CO Charlotte, NC Jackson, TN Midlothian, TX St. Paul, MN Saginaw, MI Auburn, NY Birmingham, AL Wallingford, CT Flowood, MS Bourbonnais, IL Marion, OH Sedalia, MO Vidor, TX Pittsboro, Columbia City, IN; Roanoke, VA

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
905.03C Bar Reinforcement (Epoxy Coated)	ERSCO Construction Supply HYMMCO, LLC Pacific Highway Products, LLC <u>Epoxy Coating Companies</u> ABC Coating Co. ABC Coating Co. of OK, Inc. ABC Coating Co. of MI, Inc. ABC Coating Co. of IL, Inc. ABC Coating Co. of MN, Inc., Ambassador Steel Corp./Harris Rebar American Highway CMC Rebar Corrosion Control, Inc. (CCI) Harris Rebar Lane Enterprise, Epoxy Coating Div. Midwest Pipe Coatings Simcote Simcote Simcote Titusville Fabricators, Inc. Wady Industries, Inc.	Lansing and Wyoming, MI Saginaw, MI Marion, OH Tulsa, OK Wyoming, MI Manteno, IL Minneapolis, MN Bourbonnais, IL Kankakee, IL Kankakee, IL; Muncie, IN; Waxahachie, TX Auburn, NY Bethlehem, PA Carlisle, PA Schereville, IN Saint Paul, MN Marion, OH Franklin, PA Maquoketa, IA
905.06 Welded Steel Wire Reinforcement (Mesh)	Hallett Wire Products Co. Insteel Wire Products Iowa Steel & Wire Liberty Engineered Wire Products Numesh Nucor Steel Connecticut, Inc. Oklahoma Steel & Wire Co. Inc. Structural Reinforcement Products Inc. Tatano Wire Products LLC	Kingman, AZ; Jacksonville, FL; Hickman, KY; St Joseph, MO; Mt Airy, NC; Hazelton, PA; Gallatin, TN; Dayton, TX Centerville, IA Upper Sandusky and Warren, OH Glen Falls, NY Wallingford, CT Madill, OK Hazelton, PA Lemont Furnace, PA

Approved Manufacturers			
Spec. # and Material Name		Approved Manufacturers	Manufacturers Location
905.07 Strand for Prestressed Concrete		Bekaert Corporation Insteel Wire Products Liberty Strand Tech Manufacturing, Inc. RettCo Steel, LLC Sumiden Wire Products Corporation	Van Buren, AR Sanderson, FL; Gallatin, TN; Houston, TX Summerville, SC Newnan, GA Stockton, CA; Dickson, TN
905.08 Tendons for Lateral Post Tensioning		Wire Mesh Corporation (WMC)	St. Matthews, SC
908.11A Guardrail, Steel Beam Elements, Anchorage, Bridge, Shoes, Departing End Terminals (End Sections)		Contech Engineered Solutions, LLC Gregory Highway Products Highway Safety Corporation IMH Products, Inc. R.G. Steel Corporation SPIG Industry LLC Valtir, LLC	Glastonbury, CT Indianapolis, IN Pulaski, PA Abingdon, VA Lima, OH
908.11A Guardrail Approach Terminals Remarks: Approach Terminals are proprietary items, accepted as complete units. All systems must be approved by the NCHRP and MDOT Barrier Advisory Commission.	<u>Type 1</u> SRT 350 FLEAT - 350 refer to Design Std. Plans 61(X) latest version <u>Type 2</u> ET-Plus SKT - 350 refer to Design Std. Plans 62(X) latest version <u>Type 3</u> CAT FLEAT - MT refer to Design Std. Plans 63(X) latest version	Valtir, LLC * Road Systems, Inc. Gregory Highway Products R.G. Steel Corporation Highway Safety Corporation Valtir, LLC * Road Systems, Inc. Gregory Highway Products R.G. Steel Corporation Highway Safety Corporation Valtir, LLC * Road Systems, Inc. Gregory Highway Products R.G. Steel Corporation Highway Safety Corporation	*Notes: Road Systems, Inc. (RSI) developed both SKT 350 and FLEAT-350 systems. RSI does not manufacture beams. The 3 listed companies under RSI are distributors and distribute SKT and FLEAT smart parts that make-up the approved approach terminals.

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
908.12 Steel Posts for Beam Guardrail	Contech Engineered Solutions, LLC Gregory Highway Products Highway Safety Corporation IMH Products, Inc. R.G. Steel Corporation SPIG Industry LLC Valtir, LLC	Glastonbury, CT Indianapolis, IN Pulaski, PA Abingdon, VA Lima, OH
909.04A Reinforced Concrete Pipe	County Materials Corporation Green Infrastructure Partners, Inc. Northern Concrete Pipe Oldcastle Infrastructure Upper Peninsula Concrete Pipe Co.	Marathon, WI Taylor, MI Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Elgin, IL Escanaba, MI
909.04C Non-Reinforced Concrete Pipe	Green Infrastructure Partners, Inc. Northern Concrete Pipe Upper Peninsula Concrete Pipe Co.	Taylor, MI Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Escanaba, MI
909.04D Precast Concrete Box Sections	ADL Systems, Inc. Mack Industries Northern Concrete Pipe Oldcastle Infrastructure Quality Precast, Inc. Upper Peninsula Concrete Pipe Co.	Portland, MI White Lake, MI, and Toledo, OH Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Elgin, IL Kalamazoo, MI Escanaba, MI
909.04E Precast Concrete End Section For Culverts & Sewers	County Materials Corporation Northern Concrete Pipe Oldcastle Infrastructure Upper Peninsula Concrete Pipe Co.	Marathon, WI Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Elgin, IL Escanaba, MI

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
909.04G Precast Concrete Three-Sided or Arch Culverts	Design ADL Systems, Inc. Ecospan Advance Concrete Products Adspan Contech Engineered Solutions, LLC BEBO Contech Engineered Solutions, LLC Conspan Mack Industries Conspan Northern Concrete Pipe Northern Arch Northern Concrete Pipe Hyspan Peninsula Prestress, Inc. Low/Span Upper Peninsula Concrete Pipe Co. Conspan Low/Span	Portland, MI Highland, MI Huber Heights, OH Huber Heights, OH White Lake, MI Bay City, MI Bay City, MI Clarksville, MI Escanaba, MI
909.05A Corrugated Steel Pipe	Armco Steel Corporation Bark River Culvert & Equipment Co. Contech Engineered Solutions, LLC Jensen Bridge & Supply Co. Lane Enterprises, Inc. Cadillac Culvert St. Regis Culvert, Inc. Worthington Steel	South Bend, IN Escanaba, MI Mason, MI; Mitchell and South Bend, IN; Portage, WI; Shakopee, MN; Ashland and Winchester, KY; Anderson, SC and Canfield, OH Grand Rapids and Sandusky, MI Pulaski, PA Cadillac, MI Charlotte, MI Delta, OH
909.06 Corrugated Polyethylene Pipe (CPE/HDPE)	Advanced Drainage Systems, Inc.	Owosso, MI; Findlay, London and Wooster, OH
909.07B Pipe for Underdrains Corrugated Plastic Tubing (Perforated & Non-Perforated) (Wrapped & Non-Wrapped)	Advanced Drainage Systems, Inc. Baughman Tile Co., Inc. Cervell Drainage Products Hancor, Inc. Haviland Drainage Prinsco, Inc.	Napoleon, OH; Owosso and Clifford, MI Paulding, OH Lordstown, OH Findlay, OH Haviland, OH Chatsworth, IL

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
909.07C Pipe for Underdrains Underdrain Outlet 2. Corrugated Steel Pipe	Armco Steel Corporation Bark River Culvert & Equipment Co. Contech Engineered Solutions, LLC Jensen Bridge & Supply Co. Lane Enterprises, Inc. Cadillac Culvert St. Regis Culvert, Inc. Worthington Steel	South Bend, IN Escanaba, MI Mason, MI; Mitchell & South Bend, IN; Portage, WI; Shakopee, MN; Ashland and Winchester, KY; Anderson, SC; and Canfield, OH Grand Rapids and Sandusky, MI Pulaski, PA Cadillac, MI Charlotte, MI Delta, OH
909.08B Culvert, Downspouts 1. Corrugated Steel Pipe	Armco Steel Corporation Bark River Culvert & Equipment Co. Contech Engineered Solutions, LLC Jensen Bridge & Supply Co. Lane Enterprises, Inc. Cadillac Culvert St. Regis Culvert, Inc. Worthington Steel	South Bend, IN Escanaba, MI Mason, MI; Mitchell and South Bend, IN; Portage, WI; Shakopee, MN; Ashland and Winchester, KY; Anderson, SC; and Canfield, OH Grand Rapids and Sandusky, MI Pulaski, PA Cadillac, MI Charlotte, MI Delta, OH
912.05 Structural Timber & Lumber	American Timber and Steel Co., Inc. Central Nebraska Wood Preservers, Inc. Iowa Wood Preservers, Inc. John Biewer Lumber Company Straits Wood Treating, Inc. Midwest Timber Woodstock, Inc.	Norwalk, OH Sutton, NE Oskaloosa, IA Lansing and St Clair, MI Bay City, MI Edwardsburg, MI West Branch, MI

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
912.08 Wood Posts and Blocks for Guardrail and Highway Signs (Dimension Sawed)	American Timber and Steel Co., Inc. Central Nebraska Wood Preservers, Inc. Iowa Wood Preservers, Inc. John Biewer Lumber Company Straits Wood Treating, Inc. Midwest Timber Woodstock, Inc.	Norwalk, OH Sutton, NE Oskaloosa, IA St. Clair, MI Bay City, MI Edwardsburg, MI West Branch, MI
913.06 Precast Reinforced Concrete Units for Drainage Structures (Tops, Risers and Sump Bases)	Advance Concrete Products Co. Bush Concrete Products, Inc. Consumers Concrete Products Green Infrastructure Partners, Inc. County Materials Corporation Elmer's Grand Valley Concrete Products Mack Industries Mack Vault of Toledo-a Div. of Mack Industries Northern Concrete Pipe Norwalk Concrete Industries Oldcastle Infrastructure Quality Precast, Inc. Upper Peninsula Concrete Pipe Co.	Highland, MI (Specialty Items) Muskegon, MI Kalamazoo, MI Taylor, MI Marathon, WI Traverse City, MI Grand Rapids, MI White Lake, MI Bowling Green, OH Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Norwalk, OH Elgin, IL Kalamazoo, MI Escanaba, MI
913.07 Precast Concrete Bases	See Spec. 913.06, Drainage list	
913.09 Slope Pavement Blocks	4D, Inc. Bark River Concrete Products Best Block Company Carlesimo Products, Inc. Concrete Service, Inc. Consumers Concrete Products Fendt Builder's Supply, Inc. Ferguson Block Co., Inc. Grand Blanc Cement Products Jansen Block Co. Northern Concrete Pipe	Midland, MI Bark River, MI Warren, MI Farmington, MI Traverse City, MI Kalamazoo and South Haven, MI Ann Arbor and Farmington Hills, MI Davison, MI Grand Blanc, MI Grand Rapids, MI Grand Rapids, MI

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
914.07 Transverse Pavement Joints 1. Dowel Bars (Uncoated) See Spec. 914.07A for Epoxy Coating Manufacturers (Coaters).	CMC Steel CMC New Jersey CMC Tennessee Cascade Steel Rolling Mills Nucor Steel Kankakee Inc. Marion Inc. Steel Dynamics, Inc.	Sayreville, NJ Knoxville, TN McMinnville, OR Bourbonnais, IL Marion, OH Pittsboro, IN
914.07 Load Transfer Assemblies; Dowel Baskets	American Highway Barnsco Boomer Construction Materials CMT Highway, LLC Pacific Highway Products, LLC TyE Bar, LLC	Kankakee, IL Detroit, MI Detroit, MI Durant, IA Marion, OH Glassport, PA
914.07A Transverse Pavement Joints 1. Dowel Bars (Epoxy Coated) For coating info. See QPL 914.07A2 for approved material and manufacturers.	Barnsco Boomer Construction Materials CMC Paving Solutions CMT Highway, LLC Pacific Highway Products, LLC TyE Bar, LLC <u>Epoxy Coating Companies</u> ABC Coating Co. of MI, Inc. American Highway CMC Rebar CMT Highway, LLC Lane Enterprises Midwest Pipe Coating, Inc. Simcote	Detroit, MI Detroit, MI Kankakee, IL Durant, IA Marion, OH Glassport, PA Wyoming, MI Kankakee, IL Kankakee, IL East Moline, IL Carlisle, PA Schererville, IN Marion, OH
914.08 Transverse End of Pour Joint Devices B. Deformed Bars	Bar Manufacturers See Reinforcement Bar Manufacturers Spec. 905.03	Epoxy Coating Material See Reinforcement Bar, Spec 905.03C and QPL 905.03C.
914.09 Straight and Bent Tie Bars for Longitudinal Pavement Joints, (Lane Ties)	Bar Manufacturers See Reinforcement Bar Manufacturers Spec. 905.03	Epoxy Coating Material See Reinforcement Bar, Spec 905.03C and QPL 905.03C.

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
916.02 Silt Fence (full assembly) Must be assembled using a qualified geotextile fabric listed in the QPL 910.04.	ACF Environmental – Ferguson Waterworks American Excelsior Co. Inc. C.S.I. / Geo Turf, Inc. DGI Industries Environmental Protection Products Enviroscape ECM, Ltd. Geo-Synthetics Geoproducts, Inc. Hanes Geo Components. Klein Brothers Hardwood Inc. Pallen Enterprises Rhino Seed and Landscape Supply WINFAB (Willacoochee) Industrial Fabrics, Inc.	Richmond, VA Westland, MI Highland, MI Bennington, NH Williamsburg, MI Deshler, OH Waukesha, WI Birmingham, MI Charlotte, NC, Wixom and Wyoming, MI Milford, MI Conyer, GA Bradley, MI Nashville, GA
918.06 Precast Concrete Handholes & Manholes for Electrical & Telephone Connections	Advance Concrete Products Bush Concrete Products, Inc. Carlesimo Products, Inc. Consumers Concrete Products Elmer's Grand Valley Concrete Products, Inc. Hartford Concrete Products, Inc. Mack Industries Northern Concrete Pipe Norwalk Concrete Industries Oldcastle Infrastructure Quality Precast, Inc. Upper Peninsula Concrete Pipe Co.	Highland, MI Muskegon, MI Farmington, MI Kalamazoo, MI Traverse City, MI Grand Rapids, MI Hartford City and Ashley, IN White Lake, MI Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Norwalk, OH Elgin, IL Kalamazoo, MI Escanaba, MI
919.05 Wood Sign Posts	American Timber and Steel Co., Inc. John Biewer Lumber Company Straits Wood Treating, Inc. Midwest Timber Woodstock, Inc.	Norwalk, OH St. Clair, MI Bay City, MI Edwardsburg, MI West Branch, MI

Qualified Products List

The materials in this section may be accepted for use on Michigan Department of Transportation projects based on the trade name, model number, etc., as listed.

This Qualified Products List is in accordance with the 2020 Standard Specifications for Construction.

Also see Section 5.01 of the MQAP Manual.

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
502.02B Overband Crackfill	K-T 1190 AR Plus Type 2 Deery 102 Deery 103 Roadsaver 211 Roadsaver 221 1190 Elastoflex 61 Dura-Fill 1190 Dura-Fill 3405 3405 WR Meadows 1190	Bit-Mat Products Crafco, Inc. Crafco, Inc. Crafco, Inc. Crafco, Inc. Crafco, Inc. Crafco, Inc. Crafco, Inc. Maxwell Products, Inc. P&T Products, Inc. P&T Products, Inc. Pure Asphalt Company W.R. Meadows, Inc.
603.03B2 Adhesive Systems for Grouting Dowel Bars and Tie Bars for Full-Depth Concrete Pavement Repairs Note: Use these Qualified Products for grouting repairs to existing concrete in the same direction of traffic in the same lane of repair. For grouting lane ties (deformed bars positioned transverse to the direction of traffic located between traffic lanes) use QPL 712.03J, "Adhesive Systems for Structural Anchors and Lane Ties".	Ultrabond ASF-1000 Ultrabond ASF-2000 Ultrabond 1 Ultrabond 2 Ultrabond HS-1CC UltraBond HS-200 UltraBond 1300 Inject-Tite Standard Set Inject-Tite Fast Set Aka Bond Aka Bond 550XP Aka Bond 550XPP Sonneborn Rapid Gel BHS-1250 BHS-1250XP CanRez 800 Araldite AW / HW 8561 Spec Bond 201 Highway Fast Set Epoxy DeWALT AC50 DeWALT AC100+ Gold DeWALT PE1000+ DeWALT Pure50+ DeWALT Pure110+ TRU Grip HI-Modepoxy 590 Tru-Grip 591 AWA Gel Dural Fast Set Epoxy Gel	Adhesives Technology Corp. Adhesives Technology Corp. Adhesives Technology Corp. Adhesives Technology Corp. Adhesives Technology Corp. Adhesives Technology Corp. Adhesives Technology Corp. ANKR-Tite Fastening Systems ANKR-Tite Fastening Systems Axson North America (Formerly Akemi Plastics) Axson North America (Formerly Akemi Plastics) Axson North America (Formerly Akemi Plastics) BASF Construction Chemical Blackhawk Sales Company, Inc. Blackhawk Sales Company, Inc. Cansto Coatings Ciba Specialty Chemicals Corp. Conspec by Dayton Superior, Inc. Dayton Superior Corp. DeWALT DeWALT DeWALT DeWALT DeWALT DeWALT J. Dedoes, Inc. J. Dedoes, Inc. E-Chem Euclid Chemical Company
(Continued)		

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
603.03B2 Adhesive Systems for Grouting Dowel Bars and Tie Bars for Full-Depth Concrete Pavement Repairs	Dural HS Gel	Euclid Chemical Company
	Futura Bond 566	Futura Adhesives & Chemicals
	Hilti RSE DOT	Hilti, Inc.
	Redhead A7+	ITW Commercial Construction
	Redhead C6+	ITW Commercial Construction
	Redhead G5+	ITW Commercial Construction
	Epcon A7	ITW Ramset/Red Head
	Epcon-Ceramic 6	ITW Ramset/Red Head
	SurePoxy 117	Kaufman Products
	Kelipoxy II	Kelken Construction Systems
	Dynapoxy EP-430 FAST	Pecora Corporation
	Poly-Carb	Olin Epoxy-Poly-Carb (Blue Cube Operations LLC)
	Mark 198.4	Olin Epoxy-Poly-Carb (Blue Cube Operations LLC)
	Polyject/Polybac 1257	Polygem, Inc.
	Polyject/Polybac 1295	Polygem, Inc.
	Speed Bond #1	Prime Resins, Inc.
	Sikadur Injection Gel	Sika Corporation
	Sikadur 881 DBA	Sika Corporation
	Sikadur DOT-SP13	Sika Corporation
	Arcylic -Tie AT	Simpson Strong-Tie Company, Inc.
Epoxy Tie	Simpson Strong-Tie Company, Inc.	
SpecPoxy 3000 FS	SpecChem	
Dowel Bar Adhesive #5	Superior Epoxies & Coatings	
Pro Poxy 300	Unitex	
Pro Poxy 300 FAST	Unitex	
CIA Gel 7000	USP Structural Connectors	
Rezi-Weld Gel Paste	W.R. Meadows, Inc.	
Rezi-Weld Gel Paste State	W.R. Meadows, Inc.	
706.03S Penetrating Water Repellent Treatment for Concrete Surfaces (Protective Coating for Concrete)	Application Rate, <u>sq ft/gal</u> ATS-200 150-200 Barcade Silane 100C 150-200	Advanced Chemical Technologies, Inc. Euclid Chemical Company
707.02 Bushings for Pins & Link Plates	CJ Garmax	TriStar Garlock

Qualified Products List (QPL)				
Spec. # and Material Name	Product Name			Manufacturers or Suppliers
<p>712.03J Adhesive Systems for Structural Anchor & Lane Ties*</p> <p>Note: *Lane Ties defined as deformed bars positioned transverse to the direction of traffic located between lanes. For grouting dowel bars and tie bars (bars positioned to existing concrete in the direction of the traffic in the same lane as the repair) use QPL 603.03B2, "Adhesive Systems for Grouting Dowel Bars for Full-Depth Concrete Pavement Repairs".</p> <p>Note 1. Anchors shall be installed per manufacturer's recommendations with a minimum embedment depth of 12 diameters for reinforcing steel and 9 diameters for threaded bolts.</p> <p>Note 2. Material is limited to the shelf-life recommendations by the manufacturer.</p>	<u>Name</u>	<u>Adhesive Type</u>	<u>Mixing & Inject.</u>	
	Ultrabond 1	Epoxy	Yes	Adhesives Technology Corp. Adhesives Technology Corp.
	HS-200	Epoxy	Yes	
	Hilti HIT-HY 100	Urethane- Methacrylate	Yes	Hilti, Inc.
	Hilti HIT-HY 200-A V3	Urethane- Methacrylate	Yes	Hilti, Inc.
	Hilti HIT-HY 200-R V3	Methacrylate	Yes	Hilti, Inc.
	Hilti HIT RE-10	Epoxy	Yes	Hilti, Inc.
	Hilti HIT-RE-500v3	Epoxy	Yes	Hilti, Inc.
	Redhead A7+	Epoxy	Yes	ITW Commercial Construction CGM, Inc.
	Super Por-Rok	Non-Shrink Grout	Yes	
	DeWALT Pure 110+	Epoxy	Yes	Powers Fasteners, Inc.
	Sika AnchorFix 500	Epoxy	Yes	Sika Corporation
	AT-XP	Acrylic	Yes	Simpson Strong-Tie Anchor Systems
	Acrylic-Tie	Methacrylate	Yes	
	SET	Epoxy	Yes	Simpson Strong-Tie Anchor Systems
	Pro-Poxy 300	Epoxy	Yes	Unitex
	CIA-Gel 7000	Epoxy	Yes	USP Structural Connectors
Rezi Weld Gel	Paste State Epoxy	Yes	W.R. Meadows, Inc.	

Qualified Products List (QPL)		
Spec # and Material Name	Product Name	Manufacturers or Suppliers
<p>712.03K Structure Expansion Anchors (Mechanical Expansion Anchors)</p> <p>Pull-out Testing is required per MQAP Manual Section 3.03.</p> <p>Note: Mechanical Expansion Anchors shall be set by applying the manufacturer's specified torque. The turn of the nut method will not be an acceptable alternative.</p>	<p>1. Pre-Drilled Flush Type</p> <p>a) Hilti HDI (3/8", 1/2", 3/4" dia. anchors only)</p> <p>2. Pre-Drilled Stud Type - Not suitable for lane ties or for guardrail end shoes because of exposed thread.</p> <p>a) Hilti Kwik-Bolt II or Kwik-Bolt III</p> <p>3/8" dia. anchor - min. embedment = 2 1/2"</p> <p>1/2" dia. anchor - min. embedment = 3 1/2"</p> <p>5/8" dia. anchor - min. embedment = 4"</p> <p>b) Simpson Strong-Tie Wedge-All</p> <p>1/2" dia. anchor - min. embedment = 4 1/2"</p>	
<p>712.03L Mechanical Reinforcement Splicing</p> <p>Note: Splices used to connect precast structural elements shall be high strength splices.</p>	<p>BPI Barsplicer System</p> <p>Grip-Twist Threaded Position Coupler</p> <p>Taper Threaded Grip-Twist</p> <p>Zap Screwlok</p> <p>Tru-Splice Stainless Steel</p> <p>Bar-Lock L-Series</p> <p>DBDI</p> <p>Lenton</p> <p>Lenton Form Saver</p> <p>Lenton Interlok (High Strength)</p> <p>Lenton Position Coupler</p> <p>NMB Splice Sleeve (High Strength)</p>	<p>BarSplice Products, Inc., Dayton, OH</p> <p>BarSplice Products, Inc., Dayton, OH</p> <p>BarSplice Products, Inc., Dayton, OH</p> <p>BarSplice Products, Inc., Dayton, OH</p> <p>Contractors Materials Company, Cincinnati, OH</p> <p>Dayton Superior Corp., Miamisburg, OH</p> <p>Dayton Superior Corp., Miamisburg, OH</p> <p>PENTAIR, Solon, OH</p> <p>PENTAIR, Solon, OH</p> <p>PENTAIR, Solon, OH</p> <p>PENTAIR, Solon, OH</p> <p>Splice Sleeve North America, Inc., Livonia, MI</p>
<p>712.03Y Embedded Galvanic Anodes</p>	<p>MasterProtect CP Models: 8065, 8105, 8150</p> <p>Sentinel-GL</p> <p>Sika Galvashield XP</p> <p>Sika Galvashield XP+</p> <p>Sika FerroGard 650, 670, 675</p> <p>Galvashield XP</p> <p>Galvashield XP+</p> <p>Galvashield XPC</p> <p>Galvashield XPT</p>	<p>BASF Chemical Company</p> <p>Euclid Chemical Co.</p> <p>Sika Corporation</p> <p>Sika Corporation</p> <p>Sika Corporation</p> <p>Vector Corrosion Technologies</p> <p>Vector Corrosion Technologies</p> <p>Vector Corrosion Technologies</p> <p>Vector Corrosion Technologies</p>

Qualified Products List (QPL)		
Spec # and Material Name	Product Name	Manufacturers or Suppliers
713.02B Sealant for Perimeter of Beam Repairs Note: No silicone materials - only polyurethane (PU) or PU blended materials that are paintable. Typically 1 week cure prior to painting. All non-sag material.	MasterSeal NP 1 Bostik 2020 Duralink (F1200) Loxon H1 Loxon S1 Sikaflex-15LM SikaHyflex-150 LM Vulkem 116 XtraBond 9500	BASF Construction Chemicals, Shakapee, MN Bostik US Chem Link Sherwin-Williams Sherwin-Williams Sika Corporation Sika Corporation Tremco, Inc. Premier Industrial Supply
715.02 Coating Systems for New Hanger Assemblies	See Coating Systems for Steel Structures, Hanger Assemblies and End Diaphragms QPL 915	
715.02 Abrasive, Low Dusting Note: The blasting profile produced by these abrasives will depend on the equipment used. It is the responsibility of the contractor to produce a profile within the 1.0 to 2.8 mils specified range. The abrasive additive, Blastox, may be used with any of the listed low-dusting abrasives.	20/40 40/70 KinetiX 20/70 Black Diamond Abrasive - Coal Slag GMA Garnet Blast Black Shot Granulated Slag Jetmag 32B4 StarBlast XL Emerald Creek Garnet Blackjack MSM, Waupaca Materials Black Beauty Black Beauty Fine Black Beauty Medium Sure Cut Velocity Fine Alluvial River Garnet Ebony Grit - Copper Slag International Garnet 20-40 International Garnet 30-60 Galaxy Garnet 30-60 Snapshot XL - Iron Silicate	10X Engineered Materials, Wabash, IN 10X Engineered Materials, Wabash, IN 10X Engineered Materials, Wabash, IN U.S. Minerals, Tinley Park, IL GMA Garnet Pty Ltd, Narngulu, WA, Australia Bell & MacKenzie Co. Ltd, Hamilton, Ontario Carpenter Brothers Inc., Mequon, WI The Chemours Company, Wilmington, DE Emerald Creek Garnet, Fernwood, ID Faulks Brothers Constr. Co., Inc., Waupaca, WI Harsco Environmental, Camp Hill, PA Harsco Environmental, Camp Hill, PA Harsco Environmental, Camp Hill, PA Harsco Environmental, Camp Hill, PA Harsco Environmental, Camp Hill, PA Marco Group International, Beaver Falls, PA Opta Minerals Inc. Opta Minerals Inc. Opta Minerals Inc. Opta Minerals Inc. Universal Minerals Kentucky, Inc., Louisville, KY

Qualified Products List (QPL)		
Spec # and Material Name	Product Name	Manufacturers or Suppliers
803.02B Detectable Warning Surfaces (ADA Compliant Sidewalk Ramps), 1. Cast-in-Place	Access Tile Cast In Place Replaceable	Access Products, Inc., Buffalo, NY
	Advantage Classic	Advantage Tactile Systems, Buffalo, NY
	Advantage Premier	Advantage Tactile Systems, Buffalo, NY
	AlertCast	AlertTiles, Wilmington, NC
	ADA Solutions Cast in Place Paver - Composite	ADA Solutions, Wilmington, MA
	ADA Solutions Cast in Place Replaceable - Rectangular & Radius - Composite	ADA Solutions, Wilmington, MA
	ADA Solutions Iron Dome© - Cast in Place Replaceable - Cast Iron	ADA Solutions, Wilmington, MA
	DetecTile Replaceable Tactile Panel	DetecTile Corporation
	Duralast® Detectable Warning Plates	East Jordan Iron Works, East Jordan, MI
	Armor-Tile Cast in Place Composite	Engineered Plastics, Inc., Williamsville, NY
	NF Detectable Warning Plate	Neenah Foundry Company, Neenah, WI
	TufTile	TufTile, Inc.
	TufTile Galvanized Steel Tile	TufTile, Inc.
	TufTile Polymer Tactile Tile	TufTile, Inc.
2. Surface Applied*	ADA Solutions Surface Applied - Composite	ADA Solutions, Wilmington, MA
*Note: Surface applied detectable warning surfaces may only be used to retrofit existing concrete	Alerttile	Detectable Warning Systems, Wilmington, NC
	Armor-Tile Surface Applied Composite Warning System	Engineered Plastics, Inc., Williamsville, NY

Qualified Products List (QPL)			
Spec # and Material Name	Product Name		Manufacturers or Suppliers
811.03D1 Waterborne, Liquid Pavement Marking Material	<u>Product ID</u>	<u>Color</u>	Sherwin-Williams Sherwin-Williams Sherwin-Williams Sherwin-Williams Ennis-Flint Ennis-Flint Ennis-Flint Ennis-Flint Ennis-Flint Ennis-Flint Ennis-Flint Ennis-Flint Ozark Materials, LLC Ozark Materials, LLC
	TM-2582	White	
	TM-2204	White	
	TM-2583	Yellow	
	TM-2205	Yellow	
	982211	White	
	982212	Yellow	
	982221	White	
	982222	Yellow	
	982201	White	
	982202	Yellow	
	985205	Blue	
	985203	Black	
	14228	White	
24228	Yellow		
811.03D2 Low Temperature Waterborne, Liquid Pavement Marking Material	<u>White</u>	<u>Lead Free Yellow</u>	Ennis-Flint Sherwin-Williams
	985351	985352	
	TM2372	TM2373	
811.03D3 Regular Dry Paint, Liquid Pavement Marking Material	<u>White</u>	<u>Lead Free Yellow</u>	Sherwin-Williams Ennis-Flint
	TM-5604	TM-5607	
	982271	982282	

Qualified Products List (QPL)		
Spec # and Material Name	Product Name	Manufacturers or Suppliers
811.03D6 Thermoplastic, Sprayable, Liquid Pavement Marking Material	<u>White</u>	<u>Yellow</u>
	01-WAK-BADA	01-YAK-AADA
	01-WHK-BADA	01-YHK-AADA
	0321012	0321212
	W1SS7056	Y1SS7006
	W2SS7056	Y2SS7006
	617496 Thermodrop	
		617369 Thermodrop
	884822	883241
	884822PT	883241PT
	884824	883240
	ED-9951-WHT-000	
		ED-9952-YEL-000
	11128	21128
	1157MWHSI	2798MYHSI
3023MWASI	3021MYASI	
811.03D7 Polyurea, Liquid Pavement Marking Material	5000 LPM	White
	5001 LPM	Yellow
	LS90	White and Yellow
	HPS-5	White and Yellow
	FT988	White and Yellow
811.03D8 Modified Epoxy, Liquid Pavement Marking Material	HPS-4	White and Yellow
	MFUA-10	White and Yellow
811.03D9 Preformed Thermoplastic, Preformed Pavement Marking Material	Tuff-Mark Preformed Thermoplastic	Crown USA, Inc.
	PreMark	Ennis-Flint
	PreMark XF	Ennis-Flint
	HotTape	Ennis-Flint
	Preformed Thermoplastic	Gentem Inc.
	OPTAMARK	Geveko Markings
	Preformed Thermoplastic	Ozark Materials, LLC
SWARCO Preformed Thermoplastic	Swarco	

Qualified Products List (QPL)

Admixtures for Concrete
 Air Entraining - ASTM C 260; Chemical - ASTM C 494
 (See Notes Following Listing of Admixtures)

Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01 Air Entraining Admixtures	<u>EUCLID CHEMICAL CO.</u> Eucon AEA 92	AE	Air-entraining	1.5
	Accelguard G3	E	Water-reducer accelerator (non-chloride)	16 - 90
903.02 Liquid Chemical Admixtures	Accelguard NCA	C	Accelerator (non-chloride)	15
	Eucon Air Mix 200	AE	Air-entraining	3
	EUCON Air MAC6	AE	Air-entraining	0.5 - 4
	EUCON MR	A	Water-reducer	4.5
		MR	Mid-range water-reducer	5.5
		F	High-range water-reducer	12
	EUCON MRX	MR	Mid-range water-reducer	3.5
		F	High-range water-reducer	7.5
	EUCON SE	A	Water-reducer	2.5
		D	Water-reducer retarder	4.5
	EUCON WR	A	Water-reducer	2.5 - 10
		D	Water-reducer retarder	2.5 - 10
	EUCON WR-91	A	Water-reducer	3
		MR	Mid-range water-reducer	5
		D	Water-reducer retarder	6
	EUCON A+	A	Water-reducer	3.5
	MR	Mid-range water-reducer	4.5	
EUCON Retarder75	D	Water-reducer retarder	3.5	
EUCON Stasis	D	Water-reducer retarder	1 - 16	
EUCON AIR MAC12	AE	Air-entraining	1.5 - 4	
PLASTOL 5700	F	High-range water-reducer	2 - 10	
PLASTOL 6400	F	High-range water-reducer	4.5 - 12	
PLASTOL 6420	MR	Mid-range water-reducer	2 - 5.5	
	F	High-range water-reducer	5.5 - 10	
PLASTOL ULTRA 209	F	High-range water-reducer	3.5 - 12	
(Continued)				

Qualified Products List (QPL)

Admixtures for Concrete
 Air Entraining - ASTM C 260; Chemical - ASTM C 494
 (See Notes Following Listing of Admixtures)

Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01 Air Entraining Admixtures	<u>GCP APPLIED TECHNOLOGIES, INC.</u>			
	ADVA 140M	A	Water-reducer	5 - 9
903.02 Liquid Chemical Admixtures	ADVA 405	F	High-range water-reducer	9 - 16
	ADVA Cast 198	F	High-range water-reducer	11 - 18
	ADVA Cast 575	F	High-range water-reducer	4 - 15
	ADVA Cast 585	F	High-range water-reducer	3.5 - 10
	ADVA Cast 600	F	High-range water-reducer	4 - 10
		A	Water-reducer	2 - 4
		F	High-range water-reducer	4 - 10
		F	High-range water-reducer	11-18
		F	High-range water-reducer	6 - 20
		C	Accelerator (non-chloride)	15
		AE	Air-entraining	1
		AE	Air-entraining	0.5 - 5.0
		AE	Air-entraining	1 - 5
		F	High-range water-reducer	6 - 20
		A	Water-reducer	4.5
	MR	Mid-range water-reducer	6 - 12	
	F	High-range water-reducer	12 - 15	
	A	Water-reducer	2.0 - 6.0	
	F	High-range water-reducer	10 - 15	
	MR	Mid-range water-reducer	6.0 - 10.0	
	MR	Mid-range water-reducer	9 - 12	
	F	High-range water-reducer	12 - 15	
	C	Accelerator (non-chloride)	8 - 60	
	D	Water-reducer retarder	2.5 - 6	
	AE	Air-entraining	1.5	
	A	Water-reducer	3	
	A	Water-reducer	4 - 7	
	D	Water-reducer retarder	2 - 7	
	D	Water-reducer retarder	6 - 12	
(Continued)				

Qualified Products List (QPL)

Admixtures for Concrete
 Air Entraining - ASTM C 260; Chemical - ASTM C 494
 (See Notes Following Listing of Admixtures)

Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01 Air Entraining Admixtures	MAPEI Corporation Dynamon NRG 1092 Dynamon SX	F A F MR	High-range water-reducer Water-reducer High-range water-reducer Mid-range water-reducer	5-14 2 - 3 6 - 12 3.5 - 6
903.02 Liquid Chemical Admixtures	Mapeplast KB 1200 Polychem Paver Plus Mapeair VR Mapeair SA Polychem SA-14 Mapeair SA-50 Mapeplast 400 NC Mapefast Super Set Mapefast Super Set II Polychem Super Set Plus Mapetard R Polychem RENU Polychem SPC	A MR A AE AE AE AE A C E C E D D F	Water-reducer Mid-range water-reducer Water-reducer Water-reducer Air-entraining (vinsol resin) Air-entraining Air-entraining Air-entraining Water-reducer Accelerator (non-chloride) Water-reducer accelerator (non-chloride) Accelerator (non-chloride) Water-reducer accelerator (non-chloride) Water-reducer retarder Water-reducer retarder High-range water-reducer	3 - 5 5 - 8 2 - 8 0.5 0.4 - 3.0 0.5 - 3.0 1 - 3 2 - 5 16 - 32 10 16 - 90 10 3 - 5 3 5.5
(Continued)				

Qualified Products List (QPL)

Admixtures for Concrete
 Air Entraining - ASTM C 260; Chemical - ASTM C 494
 (See Notes Following Listing of Admixtures)

Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt	
903.01 Air Entraining Admixtures	<u>Master Builder Solutions US LLC.</u>				
	MasterSet DELVO	D	Water-reducer retarder	3	
903.02 Liquid Chemical Admixtures	MasterGlenium 3400	F	High-range water-reducer	3	
	MasterGlenium 7500	A	Water-reducer	1.5	
	MasterGlenium 7700		F	High-range water-reducer	3 - 15
			F	High-range water-reducer	4 - 15
			F	High-range water-reducer	4
			A	Water-reducer	1.7
			MR	Mid-range water-reducer	2.6
			F	High-range water-reducer	3.2
		MasterGlenium 7920	F	High-range water-reducer	4
			MR	Mid-range water-reducer	2
		MasterGlenium 7925	F	High-range water-reducer	4
			MR	Mid-range water-reducer	2
		MasterAir AE 90	AE	Air-entraining	1
		MasterAir AE 200	AE	Air-entraining	1
	MasterAir AE 400	AE	Air-entraining	0.5	
	MasterPolyheed 900	A	Water-reducer	4	
		MR	Mid-range water-reducer	7	
	MasterPolyheed 997	A	Water-reducer	3	
		MR	Mid-range water-reducer	6	
		F	High-range water-reducer	10	
MasterPolyheed 1725	A	Water-reducer	2.5 - 4		
	MR	Mid-range water-reducer	5.5 - 7		
	F	High-range water-reducer	8 - 12		
MasterPolyheed 100	A	Water-reducer	4		
	MR	Mid-range water-reducer	8		
MasterPozzolith 200	A	Water-reducer	2		
	D	Water-reducer retarder	4		
MasterPozzolith 700	A	Water-reducer	2		
	D	Water-reducer retarder	5		
MasterSet AC 534	C	Accelerator (non-chloride)	10		
MasterSet AC 534V1	C	Accelerator (non-chloride)	10		
MasterSet FP 20	C	Accelerator (non-chloride)	10		
MasterGlenium 7511	A	Water-reducer	2 - 4		
	MR	Mid-range water-reducer	4 - 6		
	F	High-range water-reducer	6 - 15		
MasterRheobuild 1000	MR	Mid-range water-reducer	9		
	F	High-range water-reducer	13		
(Continued)	Master X-Seed 66	A	Water-reducer	4	

Qualified Products List (QPL)

Admixtures for Concrete
 Air Entraining - ASTM C 260; Chemical - ASTM C 494
 (See Notes Following Listing of Admixtures)

Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt		
903.01 Air Entraining Admixtures	<u>Preimere Concrete</u> <u>Admixtures</u>					
	EcoFlo Green	F A MR	High-range water-reducer Water-reducer Mid-range water-reducer	8 - 16 2 - 4 5 - 8		
903.02 Liquid Chemical Admixtures	Optiflo 700	A MR	Water-reducer Mid-range water-reducer	3 - 5 5 - 10		
	OptiFlo 50	A MR D	Water-reducer Mid-range water-reducer Water-reducer retarder	3 - 5 5 - 6 6		
	OptiFlo 500	A D	Water-reducer Water-reducer retarder	2 - 3.5 3.5 - 5		
	OptiFlo MR	A MR	Water-reducer Mid-range water-reducer	3 - 5 5 - 12		
	OptiFlo N2A		F A MR G	High-range water-reducer Water-reducer Mid-range water-reducer High-range water-reducer retarder	12 - 16 3 - 6 6 - 9 13 - 15	
			OptiFlo Plus	MR	Mid-range water-reducer	5 - 12
			OptiFlo 100R	D	Water-reducer retarder	3 - 5
	ConAir	AE	Air-entraining	0.5 - 4		
	ConAir 260	AE	Air-entraining	0.5 - 4		
	ConAir X	AE	Air-entraining	0.5 - 4		
	UltraFlo 2000		A MR	Water-reducer Mid-range water-reducer	2 - 4 4 - 6	
			F	High-range water-reducer	6 - 12	
	UltraFlo 5600		MR F A	Mid-range water-reducer High-range water-reducer Water-reducer	6 - 10 10 - 24 3 - 6	
			UltraFlo DP	F	High-range water-reducer	5 - 12
	NitroCast K		E	Water-reducer accelerator (non-chloride)	10 - 90	
NitroCast NC		E	Water-reducer accelerator (non-chloride)	10 - 90		
ProLong L		D	Water-reducer retarder	2.5 - 6.5		
(Continued)						

Qualified Products List (QPL)

Admixtures for Concrete
 Air Entraining - ASTM C 260; Chemical - ASTM C 494
 (See Notes Following Listing of Admixtures)

Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01 Air Entraining Admixtures	<u>SIKA CORP.</u> Sika Plastocrete-10N	A	Water-reducer	2
	Sika Plastocrete-161	D	Water-reducer retarder	3.5
903.02 Liquid Chemical Admixtures	Sika Plastocrete-250	A	Water-reducer	3
	Sika Plastiment XR	D	Water-reducer retarder	6
	Sika AEA-14	A	Water-reducer	2
	Sika AIR 260	D	Water-reducer retarder	5
	Sika AIR 360	D	Water-reducer retarder	3
	SikaControl Air-160	AE	Air-entraining	2
	Sikament AFM	AE	Air-entraining	2
		AE	Air-entraining	1
		AE	Air-Entraining	1
		A	Water-reducer	2
		MR	Mid-range water-reducer	5
		F	High-range water-reducer	10
	Sikament SPMN	MR	Mid-range water-reducer	6.5
		F	High-range water-reducer	10
	Sikament 475	A	Water-reducer	3
		F	High-range water-reducer	7
		MR	Mid-range water-reducer	5
	Sikament 686	A	Water-reducer	3
	MR	Mid-range water-reducer	5.5	
	F	High-range water-reducer	8	
SikaPlast 200	A	Water-reducer	3	
	G	High-range water-reducer retarder	13	
	MR	Mid-range water-reducer	6.5	
Sikaplast 300 GP	A	Water-reducer	5	
	MR	Mid-range water-reducer	7.5	
SikaSet NC	C	Accelerator (non-chloride)	10	
	E	Water-reducer accelerator (non-chloride)	10	
Sikatard 440	D	Water-reducer retarder	3	
Rapid - 1	C	Accelerator (non-chloride)	20	
ViscoCrete 1000	A	Water-reducer	1.5	
	MR	Mid-range water-reducer	3	
	F	High-range water-reducer	8	
ViscoCrete 2100	F	High-range water-reducer	5	
ViscoCrete 4100	F	High-range water-reducer	5	
ViscoCrete 6100	F	High-range water-reducer	5	
Viscoflow-2020	A	Water-reducer	3	
	MR	Mid-range water-reducer	6	
(Continued)				

Spec. 903 Admixture Notes:

1. Dosage Rate

The dosage rate indicated is that recommended by the producer or that used in qualification tests for approval of the admixture. There is no assurance that the desired water-reduction and/or retardation will be achieved with these dosages with a particular cement being used, as the effect is dependent on the cement chemistry, concrete temperature, and other factors. Increasing the dosage appreciably above that recommended may result in abnormal behavior of the concrete, such as extremely long or very short setting times. Reducing the dosage below that recommended may have the effect of substantially no change from concrete without the admixture. The dosage shown for retarding admixtures will normally produce a 1- to 3-hour retardation in the setting of the concrete, compared to similar concrete without the admixture, when used at normal temperatures (approximately 70°F). Increased dosage, within reasonable limits, will usually increase the retardation. Use of a retarding admixture will not slow the stiffening of concrete due to loss of slump.

2. Air-Entraining Admixtures

The contractor is responsible for verifying the compatibility of all chemical admixtures and the air-entraining admixture. If admixtures are from more than one manufacturer, run a trial batch prior to concrete placement. Provide test results for slump, air-entrainment and seven-day compression for two (2) cylinders. Actual dosage for Air-Entrainers may vary from those listed on the Qualified Products List as required by the mix design.

3. Lignin Type Admixtures

Lignin (or lignosulfonate) admixtures typically will cause the entrainment of additional air in air-entrained concrete. This type admixture does not generally entrain air by itself, but makes other air-entraining materials much more efficient. Thus, a change in dosage of either the chemical admixture or the air-entraining admixture may have a more significant effect on the air content than normally expected. It is the contractor's responsibility to be sure the specific admixture proposed for use is compatible with his operations so that excessive air content in the concrete is not developed. Most lignosulfonate type water-reducers will provide a moderate retardation if used at higher dosage rates.

4. High-Range Water-Reducers

Type F and G high range water-reducing (HRWR) admixtures (frequently called "superplasticizers") are capable of greater water reduction and greater strength gain than regular Type A water-reducers, or can provide substantial increase in slump while maintaining a cohesive concrete without loss of strength. Type G admixtures will also provide retardation of setting similar to Type D admixtures. Problems with this type of admixture include the following: (a) Loss of slump is frequently much more rapid than with plain concrete or when other admixtures are used, especially for older formulations of superplasticizers; (b) Effectiveness depends on the chemistry of the Portland cement, and the cements generally available in Michigan do not have the most favorable chemistry; (c) The air-void system may be adversely affected. Type F and G admixtures are to be used only according to the provisions of the Standard Specifications.

5. Admixtures Containing Chlorides

Some Type A and D admixtures may contain chlorides, as noted in the above listing. Section 903.03 of the Standard Specifications permits the use of these admixtures, except they are prohibited in concrete for bridge superstructure, prestressed concrete, and concrete containing galvanized steel or aluminum.

(End of Admixture Notes)

Qualified Products LIST (QPL)			
Spec. # and Material Name	Product Name		Manufacturers or Suppliers
905.03C Bar Reinforcement (Epoxy Coating) Note: Epoxy Coating Material Only. The Coating Applicator and Bar Manufacturer can be Approved Manufacturers, see Approved Manufacturers List.	<u>Epoxy Coating Product Name</u> Scotchkote FBEC 413 Resicoat RB-600 Nap-Gard 7-2719 Rebar FBE Nap-Gard 7-2750 Pureflex Green Greenbar 720A009 Greenbar 720A009LG Vectrashield PFY80006	<u>Repair Coating Product Name</u> Scotchkote 323R Thermal Chem BarPatch #803 Nap-Gard 7-1868 Nap-Gard 7-1868 Tnemec Series 66 G8925 Greenbar 920966S Vectrashield Patch Kit	3M Akzo Nobel Powder Coatings Axalta Coating Systems Axalta Coating Systems Axalta Coating Systems IFS Coatings, Inc. Valspar (Sherwin Williams) Valspar (Sherwin Williams) Valspar (Sherwin Williams)
906.09 Shear Developers (Studs)	<u>Markings</u> B C N X TW	Bluearc Stud Welding Cox Industries Nelson Stud Welding Co. (Div. of Gregory Ind.) Stud Welding Associates, Inc. Tru-Weld from Tru-Fit Products Corp.	
909.01 Recycled Rubber Adjusting Rings for Manholes and Drainage Structures	Flex-O-Ring Pivoted Turnbuckle Pro-Ring Infra-Riser Ladtech HDPE HDPE Recycled Manhole Adjusting Ring UGT Grade Ring Whirlygig	American Highway Products American Highway Products Cretex Specialty Products East Jordan Iron Works Ladtech, Inc. P. Spear Company Underground Technologies Whirlygig, Inc.	

Qualified Products List (QPL)				
Spec. #	Pipe Material	Joint System	Pipe Diameter (Inches)	Approved Manufacturers
909.03 Watertight Joint Systems	Corrugated Polyethylene Pipe	Bell/Spigot N-12WT Pro-Link Ultra WT Rubber Gasket	12 thru 60	ADS – Hancor
	Corrugated Polyethylene Pipe	Compression Gasket	12 thru 24	Baughman Tile Co.
	Corrugated Polyethylene Pipe	Haviland Smooth-Flow WT Compression Gasket	12 thru 36	Haviland Drainage Products Co.
	Corrugated Polyethylene Pipe	MaxSeal Gasket	12 thru 60	JM Eagle
	Corrugated Polyethylene Pipe	Gold Flow Corrugated SLCP Compression Gasket	12 thru 36	Prinsco, Inc.
	Corrugated Polyethylene Pipe	Gold Flow WT w/SpringSeal gaskets	12 thru 36	Prinsco, Inc
	Corrugated Polyethylene Pipe	Bell/Spigot Polyisoprene Gaskets	12 thru 60	Southeast Culvert, Inc.
	Corrugated Polyethylene Pipe	Vertex Single Compression Gasket	12 thru 60	Southeast Culvert, Inc.
	Corrugated Polyvinyl Chloride Pipe (PVC)	Integrally Formed Elastomeric Gasket, Bell/Spigot	12 thru 36	Contech Engineered Solutions, LLC
	Concrete Pipe	Single Offset Self-Lubricating Gasket, Tylox - Hamilton Kent	12 thru 24	Green Infrastructure Partners, Inc.
	Concrete Pipe	Press Seal Gasket Corp.-4G, 4F; Hamilton Kent-Tylox Super Seal; Universal Polymer & Rubber-Profile Gasket	12 thru 33	Northern Concrete Pipe, Inc.
Concrete Pipe	Press Seal Gasket Corp.-4G, 4F, O-ring, M875;	36 thru 72	Northern Concrete Pipe, Inc.	
(Continued)				

Qualified Products List (QPL)				
Spec. #	Pipe Material	Joint System	Pipe Diameter (Inches)	Approved Manufacturers
909.03 Watertight Joint Systems	Concrete Pipe	Hamilton Kent-Tylox SuperSeal Press Seal Gasket Corp.O-ring, M875;	78 thru 144	Northern Concrete Pipe, Inc.
	Concrete Pipe	Hamilton Kent	30 and 36	Oldcastle Infrastructure
	Concrete Pipe	Compression Gasket, Profile Cross Section, O-Ring Cross Section, Pipe Gasket & Supply	12 thru 24	Upper Peninsula Concrete Pipe Co.
	Concrete Pipe	Profile X-Section Gasket, Hamilton Kent	12 thru 36	County Materials Corp.
	Corrugated Metal Pipe	H12 Hugger Band with Single Bolt Bar and Strap with Compression Gasket	12 thru 24	Contech Engineered Solutions, LLC
	Corrugated Metal Pipe	Gasket-Bidco Wrap 12 x 3/8 Band	12 thru 18 Band 7 24 thru 30 Band 12 & larger Band 21	Jensen Bridge & Supply Co.
	Corrugated Metal Pipe	12 Bolted Band Angle with Compression Gasket Bidco Wrap 6 x 1/8 Band	12 thru 72	Cadillac Culvert
	Corrugated Metal Pipe	Bolted Corrugated Steel Band with Compression Gasket Ensolite IV Series	12 thru 24	St. Regis Culvert Inc.

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
909.05A1 Polymer Coated Corrugated Steel Pipe	Trenchcoat Protective Film	Valfilm USA
909.06 Class A, B and F Bury Plastic Pipe Smooth Lined Corrugated Plastic Pipe (CPE/HDPE); Corrugated Polyvinyl Chloride Pipe (CPV)	N12 Dual Wall (CPE/HDPE) A-2000 PVC (CPV) Smooth Flow (CPE) GoldFlo WT HDPE (CPE/HDPE)	Advanced Drainage Systems (ADS) Contech Engineered Solutions, LLC Haviland Drainage Products Prinsco, Inc.
909.10 Drainage Marker Post	See Delineator Posts 2. Plastic Material, QPL 919.03D	
910.04 Silt Fence Geotextile (fabric only) Fabricated Fence must be assembled by an Approved Manufacturer listed in 916.02.	LS125N ANITA-100SF ANITA-124SF ANITA-140SF Belton 940 Geoturf S1200 Geoturf S1240 Geoturf S1240OR Geoturf S1400 Kintex SF-3 GTF - 180 Propex 2130 SKAPS W100 TerraTex SF-D Willacoochee, Style 1210 WINFAB 105SF	ACF Environmental, Richmond, VA Anita Plastics, Inc., Solon, OH Anita Plastics, Inc., Solon, OH Anita Plastics, Inc., Solon, OH Belton Industries, Inc., Norcross, SC CSI Geoturf, Inc., Highland, MI CSI Geoturf, Inc., Highland, MI CSI Geoturf, Inc., Highland, MI CSI Geoturf, Inc., Highland, MI Geoproducts, Inc., Birmingham, MI LinQ Industrial Fabrics Propex Fabrics, Inc., Austell, GA Skaps Industries, Athens, GA Hanes Geo Components, Winston-Salem, NC Willacoochee Industrial Fabrics, Inc., Willacoochee, GA Willacoochee Industrial Fabrics, Inc., Willacoochee, GA

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
912.08Q Recycled Plastic Or Rubber Guardrail Offset Blocks	<u>Model</u> <u>Type B/BD, MGS-8 and MGS-8D</u> Dura-Bull Bloclout SPI #4 Diamond Block Eco-Block Mondo Block P-Block Thrie Beam Block EDEN Block Polylumber PL6814R King Block 8 in. King MASH-16 Composite Block <u>Type T/TD</u> Mondo Block Thrie Beam Block EDEN Block Polylumber King Size King Block 8 in. King MASH-16 Composite Block	Creative Building Products Diamond Roadway Products Eco-Composites LLC Mondo Polymer Technologies, Inc. Monroeville Industrial Moldings Monroeville Industrial Moldings Project Back to EDEN Ramco International Valtir, LLC Valtir, LLC Mondo Polymer Technologies Monroeville Industrial Moldings Project Back to EDEN Ramco International Valtir, LLC Valtir, LLC
914.03B Recycled Rubber Joint Filler	Reflex	The J D Russell Company
914.04A Hot-Poured Joint and Crack Sealant (Joint and Crack Sealer in Concrete Pavements, Bridges, Other Structures and HMA Rout and Seal applications)	Deery 101 ELT Roadsaver 522 3725 Elastoflex 72 MACSEAL 6690-4 MOD Dura-Fill 3725 3405-M Michigan	Crafco, Inc. Crafco, Inc. Crafco, Inc. Maxwell Products McAsphalt, Ind. P & T Products W.R. Meadows

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
914.06 Epoxy Resin Adhesive & Temporary Seal (Crack Injection)	Crackbond LR321 LV	Adhesives Technology Corp.
	Crackbond LR321 SLV	Adhesives Technology Corp.
	Akabond 817	Axson, Eaton Rapids, MI (formerly Akemi Corp.)
	Akabond 818	Axson, Eaton Rapids, MI (formerly Akemi Corp.)
	Akabond 819	Axson, Eaton Rapids, MI (formerly Akemi Corp.)
	MasterInject 1380	BASF Construction Chemical, Shakopee, MN
	MBT P&R Concesive 1360	BASF Construction Chemical, Shakopee, MN
	BHS-1617	Blackhawk Sales Co, Inc., Rock Island, IL
	BHS-1618	Blackhawk Sales Co, Inc., Rock Island, IL
	BHS-1619	Blackhawk Sales Co, Inc., Rock Island, IL
	Arndite 8560	Ciba Corporation, East Lansing, MI
	EP-SLV	E-Chem, LLC
	True Grip 150	J. Dedoes, Inc., Milford, MI
	NIP124LV	Epoxy Unlimited, Harrison Twp, MI
	CI 060	Hilti Inc., Columbus, OH
Dynapoxy EP-450	Pecora Corporation	
E Bond 550	Ridgemoor Supply, Kentwood, MI	
Sikadur 35, Hi-Mod LV	Sika Corporation, Lyndhurst, NJ	
Sikadur 52	Sika Corporation, Lyndhurst, NJ	
Pro Poxxy 50 Super LV	Unitex, Kansas City, MO	
914.07A Transverse Pavement Joint 2. Dowel Bar Coating (Epoxy)	Scotchkote 426	3M
	Resicoat RB 601	Akzo Nobel Powder Coatings
3. Alternate Bond Release Agent	Nap-Gard 7-2732P	Axalta Coating Systems, LLC
	PFR 70001	Valspar (Sherwin Williams)
914.08 Transverse Pavement Joint, Deformed Dowel Bar Coating	Bond Release Agent - Tectyl 506	Daubert Chemical
	BCG Protec 6116 DS MA	Bradley Coatings Group
914.09 Straight & Bent Tie Bars for Longitudinal Pavement Joints (Lane Ties), Coating	See Reinforcement Bar Coating, QPL 905.03C	

Qualified Products List (QPL)			
Spec. # and Material Name	Product Name	Manufacturers or Suppliers	
914.11 Preformed Waterproofing Membrane Note: Not to be used on Treated Wood Materials.	Carlisle CCW 711-Highway and Bridge Membrane Geotac Waterproofing Membrane Geotac Polyester HS Petrotac 4591 Protecto Wrap M400 AR Sealtight Mel-Dek	Carlisle Coatings and Waterproofing Crafco Inc. Crafco Inc. Propex Operating Company Protecto Wrap Co. W.R. Meadows, Inc.	
915 Coating Systems for Steel Structures, Hanger Assemblies and End Diaphragms Notes: *Indicates product can be used on faying surfaces of slip critical bolted connections which require Class "B". +Information from the Slip Coefficient and Creep Resistance Test Certificate is given for use with primed bolted connections to meet Class "B" requirements.	*Carbozinc 859 +100 hrs min cure, 6 mils max DFT, 10 oz/gal max thin Carboguard 893 Carbothane 133 VOC or LV	<u>Coats</u> 1 st 2 nd 3 rd	Carboline Company
	*Interzinc 315B +48 hrs min cure, 4 mils max DFT, no thinner allowed Intergard 475HS Interthane 870UHS	1 st 2 nd 3 rd	International Protective Coatings
	*Amercoat 68HS +168 hrs min cure, 3 mils max DFT, 4 oz/gal max thin Amercoat 399 Amercoat 450H	1 st 2 nd 3 rd	PPG Industries
	*Zinc Clad III HS +168 hrs min cure, 5 mils max DFT, 12 oz/gal max thin Macropoxy 646 Fast Cure Epoxy Acrolon 218 HS	1 st 2 nd 3 rd	Sherwin-Williams
	*Zinc Clad 4100 +72 hrs min cure, 5 mils max DFT, 6 oz/gal max thin Macropoxy 646 Fast Cure Epoxy Acrolon 218 HS	1 st 2 nd 3 rd	Sherwin-Williams
*Zinc Clad 4100 +72 hrs min cure, 5 mils max DFT, 6 oz/gal max thin Macropoxy 646 Fast Cure Epoxy Hi-Solids Polyurethane 250	1 st 2 nd 3 rd	Sherwin-Williams	

Qualified Products List (QPL)					
Spec. # and Material Name	Seed Varieties				
917.11 Seed Varieties	<u>*Kentucky Blue Grass</u>	<u>*Perennial Ryegrass</u>	<u>*Hard Fescue</u>	<u>*Creeping Red Fescue</u>	<u>*Fulfs Salt Grass</u>
Varieties of Seed on QPL Date of Testing Not to Exceed One Year	Arc Baron Bristol Brooklawn Cannon Corsair Diva Fielder Guinness Midnight Nassau	Advent Accent II Charger II Fiesta 4 Manhattan 5 Palace II Palmer III Pennant III Pepper II Pillar II Prelude III	Aurora II Aurora Gold Eureka II Gladiator Matterhorn Nanook Nordic Reliant II Reliant IV Rescue Rescue 911	Celestial Cindy Lou Dawson Epic Garnet Hector Kent Kevin Maxima 1 Ruddy Seabreeze GT Shademaster II Shoreline Silverlawn SR 5250	Fulfs Fulfs II Salty Sea Salt
Approved MDOT seed mixtures, see Table 917-2 in the Spec Book.					
*Species	NuBlue NuBlue Plus Parade Raven Rugby II SR 2100 SR 2150 Touchdown Wildwood	Premium Primary II Process Quickstart II Saguaro Savant Sideways SR 4650 SR 4660ST	Scaldis II Spartan II SR 3150 Sword		

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
917.14B1 Turf Mulch Blankets, High Velocity Mulch Blankets (Two Sided Net)	AEC Premier Straw Highway Double Net	American Excelsior Co.
	Curlex II	American Excelsior Co.
	Contech High Velocity ERO-MAT	Contech Engineered Solutions, LLC
	ECS-2 Mulch Blanket	East Coast Erosion Control Blankets
	Enviroscape HV Straw Mulch Blanket S2000	Enviroscape ECM
	S2000D Straw Blanket	Enviroscape ECM
	ECB EX32	ErosionControlBlanket
	ECB S32	ErosionControlBlanket
	S2 Erosion Control Blanket	S.I. Geosolutions / Land
	ECS-2D	Hanes Geo Components
	Erosion Control Blanket DS-150	North American Green
	Erosion King High Velocity Double Net	Rhino Seed & Landscape Supply
	Excel SS-2 (Regular)	Western Excelsior Corp.
WinterStraw HVW	Winters Excelsior Company	
917.14B2 Turf Mulch Blankets, Mulch Blankets (Single Sided Net)	AEC Premier Straw Highway Single Net	American Excelsior Co.
	Curlex 1-CL	American Excelsior Co.
	Curlex I	American Excelsior Co.
	Contech ERO-MAT	Contech Engineered Solutions, LLC
	Futerra Mulch Blanket	Profile Products, LLC
	ECS-1 Mulch Blanket	East Coast Erosion Control
	ECS-1D Mulch Blanket	East Coast Erosion Control
	Enviroscape Straw Mulch Blanket S1000	Enviroscape ECM
	S1000D Straw Blanket	Enviroscape ECM
	ECB EX31	ErosionControlBlanket
	ECB S31	ErosionControlBlanket
	Erosion Control Blanket DS-75	North American Green
	Erosion King Mulch Blanket	Rhino Seed & Landscape Supply
	S1 Erosion Control Blanket	Synthetic Ind. / BonTerra America
	ERO-MAT V75S	Verdyol-Canada
Excel SR-1 (Regular)	Western Excelsior Corp.	
WinterStraw SNW	Winters Excelsior Company	

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
917.14C Mulch Binders (Tackifiers)	1. Latex Base Adhesive BUTOFAN NS 268 EZ Straw Seeding Mulch w/Tack 2. Paperfiber Mulch Binders Applegate Mulch Cellin Fiber Mulch Geopro Basis Plus Hydro Green Hydroseeding Mulch Hydro Green Hydroseeding Mulch Profile Cellulose Profile Cellulose w/Tack Rhino Greenstar Rhino Greenstar Plus 3. Excelsior/Guar Gum Base Adhesive Excel Fiber Mulch Profile Wood Fiber with Tackifier 4. Guar Gum Base Adhesive Geotack EcoTak-OP5 Finn A500 Hydro-Stik Landtack ConTack Lawn Tack 5. Hydrophilic Polymers Agro Tack MP Exact-Tac (E-T) Geotack II Con-Tack A/T Eco-Tak-SAT 11 RMB Plus	BASF Corp. Rhino Seed & Turf Supply Applegate Insulation System Cellin Manufacturing, Inc. Hanes Geo Components Nu-Wool, Inc. Nu-Wool, Inc. Profile Products, LLC Profile Products, LLC Rhino Seed & Landscape Supply Rhino Seed & Landscape Supply American Excelsior Co. Profile Products, LLC CSI Geoturf, Inc. Eastern Products, Inc. Finn Corporation Midwest Land Supply, Inc. Profile Products, LLC Rhino Seed & Landscape Supply Agro Diversified Industries American Excelsior Co. CSI Geoturf, Inc. Profile Products, LLC Eastern Products, Inc. Reinco Mulch Binder Corp

Qualified Products List (QPL)					
Spec. # and Material Name	Product Name				Manufacturers or Suppliers
918.06D Light Weight Composite Handholes	Armorcast Box and Cover Assembly A6001640TAPCX12 PHA Series Hand Holes Quazite Box PG1730BA12 & Cover PG1730HA Polymer Concrete Pull Box & Cover FCA 173012 Duralite – 1118-18, 1212-12, 1730-24, 2436-36, & 3048-36 Synertech Underground Enclosure S1730B12FA & Cover S1730HBB0A				Arborcast Products Company Highline Products, Inc. Hubbell NewBasis Oldcastle Infrastructure Synertech Molded Products
918.08C Light Standards, Frangible Transformer Bases	11 Inch Bolt Circle TB1-17 Modified TB2-17 13 Inch Bolt Circle TB1-17 TB1-17 Modified				Akron Foundry Co. Akron Foundry Co.
919.02B1 Reflective Sheeting	<u>Type III</u> Series 3870 -- Nikkalite Ultralite Grade II --	<u>Type IV</u> Series 3930 T-6500 Series Nikkalite CRG 94000 Series 5900 Series	<u>Type IX</u> Series 3990 T-9500 Series -- 7900 Series	<u>Type XI</u> Series 4000 T-11500 Series -- --	3M Avery Dennison Nippon Carbide Industries (USA) Inc. ORAFOL Americas Inc.

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
919.03D Delineator Post, Plastic, Flexible 1. Ground Mount	Flexi-Guide 400 Series	PEXCO, Davidson Traffic Control Products
	Flexi-Guide 500 Series	PEXCO, Davidson Traffic Control Products
2. Surface Mount	Flexstake HD 600 Series	Flexstake
	Flexstake HD 650 Series	Flexstake
	Flexstake TM 750 Series	Flexstake
	Safe-Hit 248GP3	Valtir, LLC
	Shur-Flex Driveable Delineator	Shur-Tite
	Safe-Hit SQR-LOC Flexible Delineator	Valtir, LLC
	IRS Multipurpose Delineator Post	Impact Recovery Systems
	City Post	PEXCO, Davison Traffic Control Products
	Flexi-Guide FG 300 Model UR	PEXCO, Davison Traffic Control Products
	Flexi-Guide FG 300 Model EFX	PEXCO, Davison Traffic Control Products
TSM Series Flexible Delineator Post	PEXCO, Davison Traffic Control Products	
K71 Flexible Marker Post	US Reflector	
SM 700 Series	Flexstake	
TM 750 Series	Flexstake	
Shur-Flex Surface Mount Delineator	Shur-Tite	
U-Flex	Shur-Tite	
920.02C Wet Reflective Optics	Connected Roads All Weather Elements Series 50/51	3M
	Reflective Elements Series All Weather 50/51	3M
	Visi-Ultra Duralux	Potters Industries LLC Swarco Industries, Inc.
921.05A Steel Clamps for Traffic Signal Strain Poles	Strain Clamps	Utility Metals

Qualified Products List (QPL)										
Spec. # and Material Name	Product Name	Manufacturers or Suppliers								
922.06A Temporary Traffic Control, Temporary Pavement Markings Type R and NR Tape Paint - See Specific Paint Type in QPL 811.03D *WR Tape is wet-night retro reflective	<table border="0"> <tr> <td><u>White (Type)</u></td> <td><u>Yellow (Type)</u></td> </tr> <tr> <td>710 (WR) (R)</td> <td>711 (WR) (R)</td> </tr> <tr> <td>Deltaline TWR (R)</td> <td>Deltaline TWR (R)</td> </tr> <tr> <td>Visaline TWR (NR)</td> <td>Visaline TWR (NR)</td> </tr> </table>	<u>White (Type)</u>	<u>Yellow (Type)</u>	710 (WR) (R)	711 (WR) (R)	Deltaline TWR (R)	Deltaline TWR (R)	Visaline TWR (NR)	Visaline TWR (NR)	3M Brite-line Technologies, LLC Volare/ Swarco Industries, Inc
<u>White (Type)</u>	<u>Yellow (Type)</u>									
710 (WR) (R)	711 (WR) (R)									
Deltaline TWR (R)	Deltaline TWR (R)									
Visaline TWR (NR)	Visaline TWR (NR)									
922.06B Temp. Raised Pavement Markers	Type 1: Model 932 Chip Seal Marker TRPM Chip Seal Marker Type 2: Model 932 Overlay Marker Temporary Overlay Marker Type 3: Stimsonite Model 88	Apex Universal, Inc. PEXCO, Davidson Traffic Control Products Apex Universal, Inc. PEXCO, Davidson Traffic Control Products Stimsonite Corporation								
922.06C Temporary Pavement Marking, Pavement Marking Cover	<table border="0"> <tr> <td><u>Black (Type)</u></td> <td><u>Other (Type)</u></td> </tr> <tr> <td>ATM-19-285</td> <td></td> </tr> <tr> <td>3M-715</td> <td></td> </tr> </table>	<u>Black (Type)</u>	<u>Other (Type)</u>	ATM-19-285		3M-715		ATM 3M		
<u>Black (Type)</u>	<u>Other (Type)</u>									
ATM-19-285										
3M-715										

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
1005.02B Non-Shrinking Mortar and Grout Type H-1(Non-Metallic) Pre-Mixed H-2 eliminated.	MBT 928 Grout	BASF Construction Chemical, Shakopee, MN
	MasterFlow 100	BASF Construction Chemical, Shakopee, MN
	Set Grout	BASF Construction Chemical, Shakopee, MN
	Boomer Premium Grout	Boomer Construction Materials, Detroit, MI
	Upcon Super Flow Grout	Bostik Const. Prod. Co., Cleveland, OH
	Celtite 10-50 Hi-Flow	Celtite Inc., Georgetown, KY
	Conset Grout-XT	ChemMasters, Madison, OH
	Conspec 100	Conspec by Dayton Superior, Kansas City, KS
	Enduro 50 Grout	Conspec by Dayton Superior, Kansas City, KS
	Gifford-Hills Supreme Grout	Cormix, Inc., Cleveland, OH (form. Gifford-Hill)
	1107 Advantage Grout	Dayton Superior, Kansas City, KS
	Sure Grip Grout	Dayton Superior, Kansas City, KS
	NS Grout	Euclid Chemical Co., Cleveland, OH
	Five Star Grout	Five Star Products, Inc.
	Pro-Grout 90	G.C.M., Inc., Bensalem, PA
	SureGrout	Kaufman Products, Inc., Baltimore, MD
	Crystex	L&M Construction Chemicals, Inc., Omaha, NE
Duragrout	L&M Construction Chemicals, Inc., Omaha, NE	
Quikrete Precision Grout	Quikrete Technical Center, Atlanta, GA	
SC Miltipurpose Grout	SpecChem	
Superb Grout 611	Specco Industries, Lemont, IL	
Sealite 588 Grout	W. R. Meadows, Inc., Elgin, IL	

Qualified Products List (QPL)			
Spec. # and Material Name	Product Name	Manufacturers or Suppliers	
1006 Prepackaged Hydraulic Fast Set* Mortar Note: *Percentage based upon weight of prepackaged bag containing both cement and sand. Example Calculation: 50 lb bag approved at 60% extension = 50 x 0.60 = 30 lb coarse aggregate per bag.		Max. Aggregate Extension, %	
	MasterEmaco T 1060	60*	BASF Construction Chemical
	MasterEmaco T 545	60*	BASF Construction Chemical
	Burke Fast Patch 928	50*	Edoco, a Dayton Superior Co., Kansas City, KS
	Chem Speed 65	50*	Chem Masters
	HD-50 Heavy Duty Concrete Patch	60*	Dayton Superior Corp.
	Express Repair	60*	Euclid Chemical Co.
	FasTrac 246	0*	FasTrac Construction Products
	Five Star Highway Patch	60*	Five Star Products, Inc.
	Durapatch Hiway	50*	L&M Construction Chemicals, Inc.
	Planitop 18	60*	Mapei Corporation
	Planitop 18ES	40*	Mapei Corporation
	Commercial Grade Fast Set 45.5* DOT Mix		Quikrete

Selecting and Shipping Samples

The following instructions will apply for the selection, identification, and shipment of samples unless otherwise specified:

1. Samples shall be selected with care and shall be representative of the material sampled.
2. Pack samples to withstand rough shipment. Liquid materials shall be shipped in screw-top cans or friction-top cans with lids soldered in place unless otherwise specified or required. Friction-top cans with lids not soldered in place and glass jars must be surrounded and packed with suitable absorbent material in sufficient quantity to absorb all the liquid if the tops of the cans should come off or the glass jars should become broken. All packages containing liquid samples shall be marked "Fragile-Liquid."

Mark pipe, tile, and concrete test specimens conspicuously, "Handle with Care-Fragile."

3. The sample identification form must be legibly prepared and filled out in detail. All available information for proper identification of the sample shall be given including the lot number, batch number, serial number, or other identification marks.

The sample identification form shall be securely attached to the container in which the sample is shipped by means of a tag envelope. Also, include duplicate identification sheet inside wrappings, or if shipped in cloth sack, inside the sack.

4. Aggregate samples shipped to the Testing Laboratory shall be shipped in a closely woven bag. Do not use sacks which have contained sugar.
5. Cement and Pozzolanic Admixtures shall be shipped in plastic lined cloth bags.
6. The method of transportation of the samples will depend on the size, weight or quantity of material being shipped, and the time element. Small and light-weight samples shall be sent via UPS, bus, parcel post, or express. Large and heavy-weight samples shall be sent by motor freight. The sampler, being familiar with conditions, shall make shipment in the manner deemed most appropriate and economical.
7. Cloth bags, plastic liners, screw-top cans and friction-top cans may be obtained from the Laboratory. All containers must be clean and free from foreign materials. Cloth bags or sacks must be clean, free from tears or holes, and tightly woven to prevent loss of fine material.
8. All samples shall be consigned to the Michigan Department of Transportation, Construction Field Services Division, Secondary Governmental Complex, 8885 Ricks Road, Lansing, Michigan 48909, unless otherwise noted.

Appendix

Visual Inspection Items - Alphabetical

This list is intended as a quick reference, alphabetical by material name, for materials which normally require some form of testing but have VI quantities listed. It does not include materials which are accepted by VI basis only.

Visual Inspection Items - By Specification Number

This list is intended as a quick reference, by specification number for materials which normally require some form of testing but have VI quantities listed. It does not cover materials which are accepted on a VI basis only.

This Visual Inspection Items List is in accordance with the 2020 Standard Specification for Construction.

Visual Inspection Items - Alphabetical

SEC.	Material	Maximum V.I.
909	Acrylonitrile-Butadiene-Styrene (ABS) Pipe for Underdrain	600 ln ft
919	Aluminum Sheet	100 sq ft
902	Aggregate, Coarse	100 tons
902	Aggregate, Dense-Graded	500 tons
902	Aggregate, Fine	100 tons
902	Aggregate, Open-Graded	100 tons
904	Asphalt, Liquid (RC-250)	5 gal - 150 lbs
905	Bar Reinforcement (all)	500 lbs
914	Bituminous Fiber Joint Filler	150 sq ft
914	Bolts for Structure Exp. Anchor	250 units
914	Bond Release	20 gal max
922	Calcium Chloride Solids	5000 lbs
922	Calcium Chloride Solutions	1000 gals
Misc.	Cast & Ductile Iron Pipe	250 ft
901	Cement	45 tons
Misc.	Clay Pipe	10 pcs
913	Clay and Sand Lime Brick	1000 pcs
913	Concrete Block	1000 pcs
913	Concrete Brick	1000 pcs
909	Concrete Pipe, Non-Reinforced	10 pcs
909	Concrete Pipe, Reinforced & Elliptical	5 pcs of 42" dia or less
Misc	Corrugated Galv. Steel Plates	10 plates
909	Corrugated Aluminum Sheets	25 sheets
909	Corrugated Aluminum Alloy Pipe	250 ln ft
909	Corrugated Plastic Pipe	<12 in dia 250 ft
	“ “	>12 in dia 100 ft
909	Corrugated Plastic Pipe, Smooth Lined	Same as CPP
909	Corrugated Plastic Tubing for Underdrains	250 ft
909	Corrugated Steel Pipe	*
	12" or less	125 ln ft
	15" to 54"	50 ln ft
	60" or greater	25 ln ft
909	Corrugated Steel Pipe for Underdrains	*
909	Corrugated Steel Sheets	*
	12" or less	125 ln ft
	15" to 54"	50 ln ft
	60" or greater	25 ln ft
909	Coupling Bands	5 pcs
914	Deformed Bars	500 lbs
919	Delineator Posts, Steel	80 posts
919	Delineator Reflectors (Plastic and Reflective Sheeting)	25 pcs each color
914	Dowel Bars	1200 pcs
918	Electrical Conduit, Plastic	400 ln ft
918	Electrical Conduit, Rigid	400 ln ft

Visual Inspection Items - Alphabetical

SEC.	Material	Maximum V.I.
914	Epoxy Binder	5 gals
Misc.	Fiberglass and Bit. Cotton Fabric	5 rolls
910	Geotextile Blanket	500 sq yd
910	Geotextile Liner/ Riprap	500 sq yd
910	Geotextile Liner/Heavy Riprap	500 sq yd
910	Geotextile Stabilizer/Separator	500 sq yd
916	Geotextile Silt Fence	500 ln ft
920	Glass Beads, Standard	500 lbs
902	Granular, Class I	100 tons
902	Granular, Class II (Subbase)	500 cu yd
902	Granular, Class II (Abutment b.f.)	100 cu yd
902	Granular, Class IIA	500 cu yd
902	Granular, Class III	500 cu yd
902	Granular, Class IIIA	100 cu yd
908	Guardrail Beam Elements/End Sections	125 ln ft
908	Guardrail Posts, Steel	25 posts
918	Handholes, Precast Concrete	10 pcs
907	High Tensile Wire Fence (Wire)	250 ft
903	Insulating Blanket	10 sheets
903	Interim Curing (Linseed Based)	50 gals
914	Joint Assemblies	Fab. Insp. Req./100 assemblies
909	Mastic (Cold-Applied Joint Sealer)	10 gals
903	Membrane Curing Compound	200 gals
908	Metallic Waterstop (Sheet Lead & Copper)	25 sq ft
902	Mineral Filler (Bit. Mixes)	10 tons
909	Polyethylene Pipe (Downspouts)	<12 in dia 250 ft
	“ “	>12 in dia 100 ft
913	Precast Concrete Bases and Sumps	10 pcs total
918	Precast Concrete Handholes	10 pcs
909	Precast Concrete End Sections	10 pcs
913	Precast Units for Dr. Structures	10 pcs total
909	PVC Pipe (Sanitary Sewer)	600 ft
907	Rail for Braces (Chain Link)	250 ft
919	Reflective Sheeting	1 roll for less than 3" width
905	Reinforcement Steel	500 lbs
917	Seed and Seeding Mixtures	100 lbs
913	Slope Paving Blocks	1000 pcs
909	Smooth Plastic Pipe for Underdrains (Outlet)	250 ft
907	Steel Chain Link Fence Fabric	250 ft
909	Steel End Sections	4 pcs
919	Steel, Galvanized Sign Posts	20 posts
907	Steel Posts/Chain Link Fence	25 line, 25 gate posts
919	Steel Posts/Delineator	80 posts
905	Steel Wire Fabric (Mesh)	500 sq yds
913	Structural Tile	1000 tiles
907	Top Rail (Chain Link)	250 ft
907	Tension Wire	500 ft
914	Tie Bars (Lane Ties)	500 lbs

Visual Inspection Items - Alphabetical

SEC.	Material	Maximum V.I.
910	Wall Drain	100 sq ft
919	Wood Sign Posts	20 posts

*See Remarks in Acceptance Requirements Section

Visual Inspection Items – by Specification Number

SEC.	Material	Maximum V.I.
901	Cement	45 tons
902	Coarse Aggregate	100 tons
902	Dense-Graded Aggregate	500 tons
902	Open-Graded Aggregate	100 tons
902	Granular, Class I	100 tons
902	Granular, Class II (Subbase)	500 cu yds
902	Granular, Class II (Abutment b.f.)	100 cu yds
902	Granular, Class IIA	500 cu yds
902	Granular, Class III	500 cu yds
902	Granular, Class IIIA	100 cu yds
902	Fine Aggregate	100 tons
902	Mineral Filler (Bit. Mixes)	10 tons
903	Membrane Curing Compound	200 gals
903	Insulating Blanket	10 sheets
903	Interim Curing (Linseed Based)	50 gals
904	Liquid Asphalt (RC-250)	5 gals
905	Bar Reinforcement (all)	500 lbs
905	Steel Wire Fabric (Mesh)	500 sq yds
907	High Tensile Wire Fence (Wire)	250 ft
907	Steel Chain Link Fence Fabric	250 ft
907	Tension Wire	500 ft
907	Top Rail (Chain Link)	250 ft
907	Steel Posts/Chain Link Fence	25 line, 25 gate posts
907	Rail for Braces (Chain Link)	250 ft
908	Metallic Waterstop (Sheet Lead & Copper)	25 sq ft
908	Guardrail Beam Elements/End Sections	125 ft
908	Guardrail Posts, Steel	25 posts
909	Reinforced Concrete Pipe & Elliptical RCP	5 pcs of 42 in dia or less
909	Non-Reinforced Concrete Pipe	10 pcs
909	Corrugated Steel Pipe	*
	12" or less	125 ln ft
	15" to 54"	50 ln ft
	60" or greater	25 ln ft
909	Corrugated Steel Sheets	*
	12" or less	125 ln ft
	15" to 54"	50 ln ft
	60" or greater	25 ln ft
909	Steel End Sections	4 pcs
909	Coupling Bands	5 pcs
909	Corrugated Aluminum Sheets	25 sheets
909	Corrugated Aluminum Alloy Pipe	250 ln ft
909	PVC Pipe (Sanitary Sewer)	600 ln ft
909	Corrugated Plastic Pipe	<12 in dia - 250 ft
	“ “	>12 in dia 100 ft
909	Corrugated Plastic Pipe, Smooth Lined	Same as CPP
909	Mastic (Cold-Applied Joint Sealer)	10 gals
909	Precast Concrete End Sections	10 pcs

Visual Inspection Items – by Specification Number

SEC.	Material	Maximum V.I.
909	Acrylonitrile-Butadiene-Styrene (ABS) Pipe for Underdrain	600 In ft
909	Corrugated Steel Pipe for Underdrains	*
909	Smooth Plastic Pipe for Underdrains (Outlet)	250 In ft
909	Corrugated Plastic Tubing for Underdrains	250 In ft
909	Polyethylene Pipe (Downspouts)	<12 in dia 250 ft
	“ “	>12 in dia 100 ft
910	Geotextile Blanket	500 sq yd
910	Geotextile Liner/Riprap	500 sq yd
910	Geotextile Stabilizer/Separator	500 sq yd
910	Geotextile Liner/Heavy Riprap	500 sq yd
910	Wall Drain	250 sq ft
913	Clay and Sand Lime Brick	1000 pcs
913	Concrete Brick	1000 pcs
913	Concrete Block	1000 units
913	Precast Units for Dr. Structures	10 pcs total
913	Precast Concrete Bases and Sumps	10 pcs total
913	Structural Tile	1000 tiles
913	Slope Paving Blocks	1000 pcs
914	Bituminized Fiber Joint Filler	150 sq ft
914	Epoxy Binder	5 gals
914	Dowel Bars	1200 bars
914	Joint Assemblies	Fab. Insp. Req./100 assemblies
914	Bond Release	20 gal max
914	Deformed Bars	500 lbs
914	Tie Bars	500 lbs
914	Bolts for Structure Exp. Anchor	250 units
916	Geotextile Silt Fence	500 ft
917	Seed and Seeding Mixtures	100 lbs
918	Precast Concrete Handholes	10 pcs
918	Electrical Conduit, Polyethylene	400 ft
918	Electrical Conduit, Rigid	400 ft
919	Aluminum Sheet	100 sq ft
919	Reflective Sheeting	1 roll for less than 3” width
919	Delineator Reflectors (Plastic & Reflective Sheeting)	25 pcs each color
919	Steel Delineator Posts	80 posts
919	Galvanized Steel Sign Posts	20 posts
919	Wood Sign Posts	20 posts
920	Glass Beads, Standard	500 lbs
922	Calcium Chloride Solids	5000 lbs
922	Calcium Chloride Solutions	1000 gals
Misc	Clay Pipe	10 pcs
Misc	Cast & Ductile Iron Pipe	250 ft
Misc	Fiberglass and Bit. Cotton Fabric	5 rolls
Misc	Corrugated Galvanized Steel Plates	10 plates

*See Remarks in Acceptance Requirements Section